



LUANGWA COMMUNITY FORESTS PROJECT



Document Prepared by BioCarbon Partners

Project Title	Luangwa Community Forests Project
Version	1.2
Report ID	BCP_LCFP_MR3
Date of Issue	15-April-2021
Project ID	PL1775
Monitoring Period	01-January-2020 to 31-December-2020
Prepared By	BioCarbon Partners
Contact	BioCarbon Partners, 5th Floor, Barkly Wharf, Le Caudan Waterfront, Port Louis, Republic of Mauritius, Telephone: +260 211 290 051, Email: info@biocarbonpartners.com, Website: www.biocarbonpartners.com

CONTENTS

1	PROJECT DETAILS.....	4
1.1	Summary Description of the Implementation Status of the Project	4
1.2	Sectoral Scope and Project Type	5
1.3	Project Proponent	5
1.4	Other Entities Involved in the Project	9
1.5	Project Start Date	13
1.6	Project Crediting Period	13
1.7	Project Location	13
1.8	Title and Reference of Methodology	18
1.9	Participation under other GHG Programs.....	18
1.10	Other Forms of Credit.....	18
1.11	Sustainable Development.....	18
2	SAFEGUARDS.....	19
2.1	No Net Harm	19
2.2	Local Stakeholder Consultation	19
2.3	AFOLU-Specific Safeguards	23
3	IMPLEMENTATION STATUS	27
3.1	Implementation Status of the Project Activity	27
3.2	Deviations	42
3.3	Grouped Projects	44
4	DATA AND PARAMETERS.....	45
4.1	Data and Parameters Available at Validation	45
4.2	Data and Parameters Monitored.....	56
4.3	Monitoring Plan.....	101
5	QUANTIFICATION OF GHG EMISSION REDUCTIONS AND REMOVALS	111
5.1	Baseline Emissions	111
5.2	Project Emissions	114
5.3	Leakage.....	117
5.4	Net GHG Emission Reductions and Removals.....	118

6	APPENDICES	123
7	ANNEX 1: LIST OF VM0009 V3.0 MR REQUIREMENTS APPLICABLE TO F-U3 BASELINE TYPE	124

1 PROJECT DETAILS

1.1 Summary Description of the Implementation Status of the Project

The Luangwa Community Forests Project is a large-scale REDD+ project implemented in Eastern and Lusaka Provinces, Zambia with an initial project area of 943,676 ha (Figure 1). It is being implemented on communal land in 12 chiefdoms falling within Game Management Areas (GMA) and two private ranches. Implementation is in partnership with the traditional authorities and the government of the Republic of Zambia. The project generates emissions reductions through avoided deforestation, using the following mitigation activities: a combination of direct conservation support (forest monitoring and encroachment prevention) engagement and capacity building with key Government and community stakeholders, and conservation incentives for the area protected: including performance-based payments delivered to empowered community stakeholders, through local institutions, and support to deforestation mitigation activities, including sustainable, improved livelihoods activities, such as conservation agriculture, harvesting of non-timber forest products, sustainable enterprise development, infrastructure development, and water provision. The baseline scenario is ongoing unplanned deforestation driven primarily by subsistence agriculture. Furthermore, communities remain impoverished and biodiversity declines due to habitat loss and increased poaching.

The project's community objective is poverty alleviation activities benefiting at least 20,000 households, specifically targeting vulnerable households and the poorest of the poor. The biodiversity objectives are maintaining a massive wildlife corridor between several national parks in the catchment of Zambia's 4th largest river system, conserving and maintaining vulnerable and endangered species through habitat protection and reduction in poaching. The climate objectives are to avoid deforestation in the project area and assist communities and biodiversity with climate change adaptation benefits through income diversification, improved farming techniques, crop diversification, and maintenance of habitat corridors. Project area boundaries were marked at validation and since then, aerial and ground patrols are conducted regularly to monitor compliance. During each monitoring period, 20 % of accounting and proxy area biomass plots and 100 % of leakage area monitoring plots are inventoried. Remote sensing imagery is used to monitor disturbance and fires while wildlife and other biodiversity indicators are monitored in bi-annual fixed transects surveys as well as random ground patrols. Ongoing and new community benefit projects are monitored by the Impact Monitoring division and their statuses are described in section 3.1

The project start and implementation date is 1 May 2015 and will be operational until 30 April 2045. The estimated emissions reduction for the 30-year project span is 83,598,204 tCO₂e at an average of 2,985,650 tCO₂e/yr. The emissions reduction for the current monitoring period (January 1st, 2020 to Dec. 31st, 2020) is 1,593,835 tCO₂e.

1.2 Sectoral Scope and Project Type

The project falls under scope 14 of the VCS, namely Agriculture, Forestry, and Other Land Use (AFOLU). The AFOLU project category is Reducing Emissions from Deforestation and Forest Degradation. This is a grouped REDD+ project implemented in Eastern and Lusaka Provinces, Zambia.

1.3 Project Proponent

Organization name	BioCarbon Partners
Contact person	Dr. Hassan Sachedina
Title	Chief Executive Officer
Address	BioCarbon Partners, 5th Floor, Barkly Wharf, Le Caudan Waterfront, Port Louis, Republic of Mauritius
Telephone	+260 211 290 051
Email	info@biocarbonpartners.com

Organization name	Luembe Community Resources Board
Contact person	Mr. Davison Mwanza
Title	Board Chairperson
Address	Luembe Community Resources Board, Luembe Chiefdom - Nyimba
Telephone	Cell: +260976555356
Email	

Organization name	Nyalugwe Community Resources Board
Contact person	Mr. Yulu Joseph Njobvu
Title	Board Chairperson
Address	Nyalugwe Community Resources Board, Nyalugwe Chiefdom - Nyimba
Telephone	Cell: +260976345724
Email	

Organization name	Mpanshya Community Resources Board
Contact person	Mr. Chrispin Chikopa
Title	Board Chairperson
Address	Mpanshya Community Resources Board, Mpanshya Chiefdom - Rufunsa
Telephone	Cell: +260979029568
Email	

Organization name	Shikabeta Community Resources Board
Contact person	Mr. Mathews Nyangu
Title	Board Chairperson
Address	Shikabeta Community Resources Board, Shikabeta Chiefdom - Rufunsa
Telephone	Cell: +260971938928
Email	

Organization name	Sandwe Community Resources Board
Contact person	Mr. George Tembo
Title	Board Chairperson
Address	Sandwe Community Resources Board, Sandwe Chiefdom - Petauke
Telephone	Cell: +260973414944
Email	

Organization name	Msoro Community Resources Board
Contact person	Mr. John Banda
Title	Board Chairperson
Address	Msoro Community Resources Board, Msoro Chiefdom - Mambwe
Telephone	Cell: +260974762844
Email	

Organization name	Malama Community Resources Board
Contact person	Mr. Edward Tembo
Title	Board Chairperson
Address	Malama Community Resources Board, Malama Chiefdom - Mambwe
Telephone	Cell: +260965697694
Email	

Organization name	Mnkhanya Community Resources Board
Contact person	Mr. Augustine Mulwangi
Title	Board Chairperson
Address	Mnkhanya Community Resources Board, Mnkhanya Chiefdom - Mambwe
Telephone	Cell: +260968037096
Email	

Organization name	Nsefu Community Resources Board
Contact person	Mr. Lovedale Lungu
Title	Board Chairperson
Address	Nsefu Community Resources Board, Nsefu Chiefdom - Mambwe
Telephone	Cell: +26097113087
Email	

Organization name	Jumbe Community Resources Board
Contact person	Mr. Musamba Phiri
Title	Board Chairperson
Address	Jumbe Community Resources Board, Jumbe Chiefdom - Mambwe
Telephone	Cell: +260976735005
Email	

Organization name	Mwanya Community Resources Board
Contact person	Mr. Ringstone Mwandila
Title	Board Chairperson
Address	Mwanya Community Resources Board, Mwanya Chiefdom - Lundazi
Telephone	Cell: +260978579302
Email	

Organization name	Chitungulu Community Resources Board
Contact person	Mr. Alex Banda
Title	Board Chairperson
Address	Chitungulu Community Resources Board, Chitungulu Chiefdom - Lundazi
Telephone	Cell: +260977672636
Email	

1.4 Other Entities Involved in the Project

Organization name	Munyamadzi Game Ranch
Role in the project	Landowner of Munyamadzi project area
Contact person	Thor Kirchner
Title	General Manager
Address	Munyamadzi Game Ranch, Nyimba, Zambia
Telephone	+260 97 8157643
Email	munyamadzi@live.com

Organization name	United States Agency for International Development (USAID)
Role in the Project	Initial Funder
Contact person	Catherine Tembo
Title	Natural Resources Specialist
Address	Embassy of the United States of America
Telephone	Subdivision 694/Stand 100 Ibex Hill Road, PO Box 320373
Email	Lusaka, Zambia 10101

Organization name	Forestry Department (FD)
Role in the project	National Government Regulatory Authority
Contact person	Mr. Ignatius N. Makumba
Title	Director
Address	Ministry of Lands and Natural Resources, Forestry Department. Kwacha House, Lusaka
Telephone	+260 211 226 131
Email	Inmakumba@gmail.com

Organization name	Department of National Parks and Wildlife (DNPW)
Role in the project	National Government Regulatory Authority
Contact person	Mr. Paul Zyambo
Title	Director General
Address	Ministry of Tourism and Arts, DNPW Chilanga, Lusaka.
Telephone	+260978290175
Email	paulzya@yahoo.com

Organization name	Ministry of Chiefs and Traditional Affairs Provincial Office
Role in the project	National Government Regulatory Authority
Contact person	Mr. Pythias Kakoma
Title	Senior Chief and Traditional Affairs Officer
Address	Provincial Office Chipata
Telephone	+260979314181 or 0966314181
Email	Pythiaskakoma@gmail.com

Organization name	Pia Manzi Wildlife Limited and Luansemfwa Safaris Limited
Role in the project	Landowner of Pia Manzi Project Area
Contact person	Diego Casilli
Title	Director
Address	P.O. Box33711, Lusaka, Zambia
Telephone	+260 211 258 057
Email	info@napoliproperty.com

Organization name	Bee Sweet
Role in the project	Support for Honey Market until expiry of contract in April 2020
Contact person	Nathan Enright
Title	Chief Executive Officer
Address	Plot No.1 Jacopo Rd Luanshya turn off ,P.O. Box 70839,Ndola, Zambia
Telephone	+260961690322
Email	nate.enright@gmail.com

Organization name	Ministry of Agriculture
Role in the project	Agricultural Extension Support
Contact person	Kennedy Kaputo
Title	Mambwe District Agriculture Coordinator
Address	P.O. Box 19, Mfuwe, Mambwe, Eastern Province, Zambia
Telephone	+260977969411
Email	kaputoken@yahoo.com

Organization name	Ministry of Agriculture
Role in the project	Agricultural Extension Support
Contact person	Philimon Lungu
Title	Lundazi District Senior Agriculture Coordinator
Address	P.O. Box 530016, Lundazi, Eastern Province, Zambia
Telephone	+260974515013
Email	philimonl@yahoo.co.uk

Organization name	Ministry of Agriculture
Role in the project	Agricultural Extension Support
Contact person	Moses Katundu
Title	Nyimba District Senior Agriculture Coordinator
Address	P.O. Box 570026, Nyimba, Eastern Province, Zambia
Telephone	+2601472500
Email	

Organization name	Ministry of Agriculture
Role in the project	Agricultural Extension Support
Contact person	Stanley Mvula Njobvu
Title	District Agriculture Coordinator
Address	Rufunsa, Lusaka Province
Telephone	+260972967670
Email	stanmavula@gmail.com

1.5 Project Start Date

MR.2

The project start date is May 1st, 2015.

1.6 Project Crediting Period

MR.3

The project crediting period is from May 1st, 2015 to April 30th, 2045 for a total of 30 years.

1.7 Project Location

The 14 first activity instances (Table 1 and Table 2) lie in the Eastern and Lusaka Provinces of Zambia and fall into the Luangwa Zambezi River ecological zone and the Central Southern and Eastern Plateau Zone (Figure 1). In addition, all the activity instances are situated in the Game Management Areas (GMA) within the Chiefdom areas. The project sites in Eastern Province are bordered by the South Luangwa National Park and Luangwa river in the north-western direction. The project area consists of two sites in Lusaka Province in Rufunsa District, one on each side of the great east road in Shikabeta and Mpanshya chiefdoms. The other nine project sites lie in the eastern province of Zambia in Mambwe, Lundazi, and Nyimba Districts. Project sites in Mambwe Districts are Mnkhangya, Jumbe, Nsefu, Malama, and Msoro. In Lundazi District there is one project site in Mwanya Chiefdom. The project area in Mwanya is bordered by Lukusuzi National Park and Luambe National Park area. There are two sites in Nyimba District one each in Nyalugwe and Luembe chiefdom. The geographic boundaries of the project area and a full description of the boundaries of each site can be found in the shapefiles and narratives in Appendix I. Below is the location map of the project area.

MR.4

Table 1. Summary of Project Area: REDD+ Project Zones under communal tenure, first activity instances.

Community Resource Board	Game Management Area	Chiefdom	Size (ha)	Forest Area (ha)
Mpanshya	Rufunsa	Mpanshya	84,530	82,183
Shikabeta	Luano	Shikabeta	118,102	111,968
Mwanya	Lower Lumimba	Mwanya	81,668	59,030
Luembe	West Petauke	Luembe	288,726	254,582
Nyalugwe	West Petauke	Nyalugwe	60,893	58,809
Msoro	Lower Lupande	Msoro	24,688	23,523
Malama	Lower Lupande	Malama	21,577	17,220
Mnkhanya	Upper Lupande	Mnkhanya	33,623	29,081
Jumbe	Upper Lupande	Jumbe	15,443	11,066
Nsefu	Upper Lupande	Nsefu	39,801	25,341
Chitungulu	Lumimba	Chitungulu	38,764	28,681
Sandwe	Sandwe	Sandwe	92,362	85,767
Total			900,177	787,251

Table 2. Summary of Project Area: REDD+ Project Zones on Private Land, first activity instances

Private Game Ranch	Chiefdom	Size (ha)	Forest Area (ha)
Munyamadzi	Luembe	18,671	16,449
Pia Manzi	Nyalugwe	24,798	22,393
Total		43,469	38,842




Figure 1. CFP REDD+ initial project areas (MR.1, MR.5).

MR.6

As described in detail in section 1.1.2 of the PD, a GIS analysis of deforestation map from 2007 to 2017 was used to identify key constraints to conversion. The two factors that stood out most prominently are distance from roads and slope. These factors make sense since roads provide access to forested areas for farmers and charcoal makers. Farmers who are responsible for most deforestation prefer to cultivate on relatively flat ground which will better hold soil moisture and is easier to work with oxen (which some farmers have). The analysis found constraints to conversion at greater than 45% slope and greater than 6.5 km distance from a road. Therefore, to calculate the project accounting area, a polygon buffer covering 6.5 km from roads was clipped from the project area. Then, areas of high slope and areas that were not forest according to the PALSAR analysis in both 2007¹ and 2015, were also removed from the accounting area polygon.

Maps of the accounting area with topography (areas great than 45% slope), roads, major rivers and perennial streams, land-use (forest map), and accounting area boundaries are shown in Figure 2, Figure 3, Figure 4, and Figure 5.

¹ This deviation from the methodology is explained and justified in section 3.2 of this report.




Figure 2. Mpanshya, Shikabeta, Nyalugwe, and Pia Manzi Accounting Areas




Figure 3. Luembe and Munyamadzi Accounting Areas




Figure 4. Sandwe, Malama, Msoro, and Mnkhangya Accounting Areas




Figure 5. Jumbe, Nsefu, Myanya, and Chitulungu Accounting Areas

1.8 Title and Reference of Methodology

VCS VM0009 V3.0 Methodology for Avoided Ecosystem Conversion.

VCS VT0001 Tool for the Demonstration and Assessment of Additionality in VCS Agriculture, Forestry, and Other Land Use (AFOLU) Project Activities, version 3.0.

VCS AFOLU Non-Permanence Risk Tool v4.0.

1.9 Participation under other GHG Programs

The project has not applied to any other GHG program.

1.10 Other Forms of Credit

The LCFP is not subject to binding emissions limits or emissions trading programs.

The project is validated under the CCB Standard Version 3.

1.11 Sustainable Development

Nationally stated sustainable development priorities in Zambia are described and monitored through 5-year national development plans. The focus of the Government of Zambia's Five-Year 7th National Development Plan (2017-2021) is on targeting economic diversification and job creation; poverty and vulnerability reduction; reducing developmental inequalities; enhancing human development; and the creation of conducive governance for a diversified economy. It sets targets for bringing additional areas of forest under sustainable management (500,000 hectares) and emphasizes measures to enhance the viability and diversification of agriculture co-operatives, farmer groups, and community forest management groups.

The 7th NDP departs from sectoral-based planning to an integrated (multi-sectoral) development approach, which recognizes the multi-faceted and interlinked nature of sustainable development. It calls for interventions to be tackled simultaneously through a coordinated approach to implementing development interventions, through clusters – involving all arms of Government, Cooperating Partners, Private Sectors, Civil Society Organisations, Faith-Based Organisation, and other interest groups. Further, the 7th NDP will be primarily implemented through programs and projects that are devolved to the districts within the tenets of decentralized planning, monitoring, and evaluation as determined by municipal and district councils. This will be done with a view of dealing with district-specific development challenges. The Districts design their own plans and monitoring and evaluation systems that will promote the integration of development priorities at the local level to provincial and national strategic areas of focus and outcomes.

In terms of supporting the implementation of the 7th NDP – the five-year target of 500,000 hectares of forest under management increased will be exceeded just through the approval of

the forest management agreements by the Director of Forestry under the initial BCP supported initiatives (943,676 ha) by just under a factor of 2. Reporting and monitoring on the LCFP contribution to the implementation of the 7th NDP is supporting at various levels. BCP is a member of the District Development Coordinating Committee which is chaired by the District Commissioner and Council Secretary in each of the Districts LCFP operates. However, through our close partnership with Government Departments and Agencies in each district, sustainable development results and achievements are reported through their respective representatives. This includes the Department of National Parks and Wildlife, Forestry Department, Ministry of Chiefs and Traditional Affairs, Ministry of Agriculture, Ministry of Community Development and Social Welfare. At the National level, BCP provides a presence on various national technical advisory committees and direct reporting as required to the line Ministries and their Departments. BCP contributes information and data to the National REDD+ Registry and Database Management System maintained by the Forestry Department. This allows the Government of Zambia to monitor REDD+ activities covering information such as Project Documents, budgets, project area datasets, Certification Standards, emission reduction quantification and Measurement, Reporting and Verification (MRV), benefit-sharing, and safeguards.

2 SAFEGUARDS

2.1 No Net Harm

The project is validated under the CCB Standard Version 3 and any potential negative impacts such as conflicts related to the equitable distribution of benefits are summarized in section 2.1.11 of the joint VCS/CCB Project Description. It is important to note that the negative impacts listed are potential impacts commonly associated with similar projects and therefore, should not necessarily be considered as significant.

The project is an avoided unplanned deforestation project and specifically aims to conserve the astounding biodiversity of the project area and benefit smallholder farmers dependent on the project area with a variety of project activities aimed at improving livelihoods through poverty reduction such as conservation agriculture and beekeeping.

2.2 Local Stakeholder Consultation

Stakeholder identification took place as part of the initial REDD+ viability assessment process that BCP undertook to identify new/potential REDD+ sites for the LCFP, beginning in 2014. The process followed can be broadly outlined as follows:

Workshops / Meetings with key Government and Community Authorities

Beginning at a national level, and then moving down to provincial, district, and Chiefdom levels, BCP held a series of workshops and meetings, in which we outlined REDD+ and explained the REDD+ viability assessment process, including two key criteria for REDD+:

- 1) Selection of a viable forest area for protection;
- 2) Documented consent from all relevant stakeholders / rights-holders.

Permissions were then received from Government and Chiefdom authorities to proceed with on-the-ground viability assessment activities, including participatory forest identification and stakeholder engagement in line with our standard Free, Prior, and Informed Consent (FPIC) protocol (Appendix E).

Initial “high level” stakeholder identification and mapping

During the initial District and Chiefdom-level workshops and meetings that were held, BCP solicited inputs from relevant Government and community authorities (namely: traditional authorities, including Chiefs / Chiefs’ representatives, and Community Resource Boards (CRBs), as legally recognized, Chiefdom-level community institutions), about who could be counted as potential stakeholders to any proposed REDD+ project, and where they were/are located, relative to the proposed forest areas under consideration for REDD+ protection. It was explained that identifying and consulting with any potential stakeholders is a verification requirement for REDD+, and more importantly, adequate stakeholder sensitization and consultation prior to project implementation is in everyone’s interest, to help ensure the sustainability of the project, by ensuring that all relevant stakeholders were consulted about, and consented to, participation in the project. It was explained that stakeholders could broadly be defined as anyone who could potentially be impacted by the proposed project (either positively or negatively), and/or anyone with potential decision-making power about whether or not to cut trees within the identified/proposed forest areas for protection.

At the District/Chiefdom level, Government and community authorities (traditional leaders) provided us with consistent feedback that, so long as a REDD+ project would be taking place on “community” land (including within a GMA), then all community members of the Chiefdom could be considered to be stakeholders since traditional authorities recognize that community forests belong to the entire community within the Chiefdom, and therefore, all recognized residents within the Chiefdom would have recognized rights, within the traditional leadership structure, to access and use forest resources within community forest areas. Initial community maps were drawn by these key stakeholders, and also confirmed and supplemented by satellite imagery, which confirmed the location of villages and settlements, near to proposed forest areas within each Chiefdom that had expressed willingness/interest to participate in the program.

Detailed Chiefdom/Village level stakeholder mapping - PRA/PLA FPIC activities

More detailed stakeholder identification and mapping took place during significant PRA/PLA techniques that were undertaken in each of the 12 partner Chiefdoms, as part of the FPIC processes that were undertaken by BCP during 2015-2017, at a community level. Our FPIC records show that these meetings were held at a Chiefdom level, in each of the 12 Chiefdoms, and that representatives from the then all 62 registered VAGs within the 12 Chiefdoms were involved in the FPIC activities. During the PRA/PLA activities that took place, community stakeholder identifications were confirmed, and maps were further refined, to ensure that significant community inputs were received to identify and include any potential stakeholder communities. Local (District) level Government officers were involved in this process, as well as representatives from Chiefdom level institutions (Chiefdom royal establishments; CRBs), as well as village-level representatives from VAGs and traditional leaders (Headmen). Meetings were also open to members of the wider community, who also participated and provided inputs. As part of the stakeholder identification process, it was described, again, that “stakeholders” included anyone who could potentially be affected by the project, and/or anyone with a recognized “right,” or even ability, to influence decision-making about whether or not to cut trees within the identified forest area for protection. Again, stakeholders at all levels confirmed that community forests were/are viewed to be collectively “owned” community resources, and as such, “stakeholders” should include all Chiefdom inhabitants, in all villages within participating Chiefdoms, as their rights to access and use forest resources were/are recognized by members of the local community, as well as the Chiefdom authorities (traditional leaders) as well as Government – who recognize the authority of community institutions and traditional leaders, on community or “customary” land, even within GMAs. As such, it was agreed that a registry of Chiefdom inhabitants and villages could essentially function as a stakeholder registry. Initial lists of villages were received from Headmen and were shared with BCP through VAG and CRB structures. These were used to inform data-collection plans, to complete an on-the-ground confirmation activity, to confirm, register, and map all stakeholders for REDD+ projects within each of the 12 partner Chiefdoms of the LCFP.

Once FPIC processes were completed, community consent was received and documented in community consent letters for REDD+ implementation, signed by Chiefdom authorities with legally recognized authority to manage community resources (Chiefs, CRBs). Once these letters were received, BCP undertook a “Stakeholder Household Registry” process, with the aim of confirming, documenting, registering, mapping, and counting community stakeholders to each REDD+ project, in every participating Chiefdom, in every VAG and village within that Chiefdom. This process was undertaken through CRBs and Village Action Groups (VAGs) as local-level community institutions and involved significant inputs, guidance, and participation of local traditional leaders (such as Headmen) to ensure that all members of their villages were registered as participants, stakeholders and beneficiaries to the project.

The data collection process was led by locally hired staff, working hand-in-hand with local traditional leaders such as village headmen, as well as representatives from local VAGs, CRBs, and Government.

The LCFP “Household Registry” now provides a comprehensive database, and map, of all stakeholders to REDD+ projects supported under the LCFP. As the processes above described, it has been informed by significant inputs from community authorities and government partners, solicited through a multitude of workshops, meetings, and PRA/PLA activities that have been undertaken as part of FPIC processes during the past three years, during which input was solicited, and received, concerning who should be counted as “stakeholders,” based on their recognized rights and abilities to inform decisions about forest protection within identified areas. The actual data collection process has taken approximately one year and has involved dozens of data collectors across all 12 Chiefdoms.

Other stakeholders are hunting concession holders that operate within the REDD+ project areas.

Project documentation has been made available to stakeholders throughout the project development process, including FPIC stakeholder sensitization activities that were initiated in 2014, and which have continued through 2017. Informational handouts clearly outlining the proposed project model, and accurately describing REDD+ activities, were developed and have been widely distributed to community (and Government) implementing partners, throughout this time. These handouts and other informational materials (such as informational posters about REDD+ and BCP) have been distributed to each of the 12 partner CRBs that BCP is working with, to implement REDD+ activities under the LCFP. Throughout nearly 3 years, from 2015-2017, BCP has provided capacity building training to CRB members, as well as local Government implementing partners, and locally hired staff, to ensure their ability to accurately explain and disseminate information about REDD+, in line with FPIC requirements. BCP staff also developed and launched a standard “sensitization program,” that provided critical information about REDD+ and the proposed activities of the LCFP, and which made information available in a multitude of local languages, presented by locally hired and trained staff, who ensured that this information was disseminated in locally appropriate ways. In combination with these sensitization programs, BCP has ensured that informational materials have been made available to local community stakeholders in each Chiefdom and that there are trained staff and implementing partners available at all times, in each Chiefdom, to undertake ongoing sensitization activities, to accurately disseminate information about REDD+, and to be available to answer any questions or concerns that stakeholders may have, at any given time.

BCP kept detailed records of all community and stakeholder meetings and further details of stakeholder consultation can be found in the LCFP Project Description.

After project validation, BCP has continued engagement with both higher-level and village level stakeholders. The details regarding the desired frequency of meetings and the records of actual meetings held are kept in an engagement tracker. See Appendix E for examples.

Monitoring results that point to serious concerns, such as encroachment within accounting and leakage areas are immediately reported once discovered to the relevant local stakeholders via our engagement teams. These critical results are then thoroughly investigated and discussed by local stakeholders and BCP. The results of the completed annual monitoring process are communicated to local stakeholders at the end of the monitoring period, soon after verification is completed. Since the results are tied to community benefits, a thorough explanation of monitoring results are communicated via our engagement teams to local stakeholders to substantiate their extent of the performance based benefits accrued. These communications occur during scheduled meetings with CFMG's and relevant community members and authorities. Appendix A contain evidence of communication agreements with CRBs regarding monitoring and verification results.

Local stakeholders have been made fully aware (via the information meetings and materials referred to above) of the requirements for an auditing team to verify the findings of the annual monitoring report, as is standard procedure, and what this auditing process will entail. This communication is part and parcel of the REDD+ project information dissemination which occur since the start of community engagement and continues to be communicated during refresher information sharing meetings. Appendix A contain evidence of agreements between BCP and CRBs outlining BCPs responsibility to communicate monitoring and verification findings (among others). Since the restrictions on travel placed by authorities in response to the global covid-19 pandemic in 2020/2021, BCP has obtained permission from Verra, local stakeholders and the auditors to conduct virtual field visits and interviews on-line, facilitated by our engagement teams. This process was communicated to our local stakeholders through formal notices to CFMGs and the Forestry Department (see Appendix E) and via both higher- and lower-level community engagement meetings.

2.3 AFOLU-Specific Safeguards

Negative Local Stakeholder Impact Mitigation

The measures to mitigate negative impacts to poachers are driven by a combination of job creation and livelihood alternatives. The project has created more than 60 community jobs, mainly for Community Scouts (CS). These CS are hired through BCP support via CRB contracts and their role is to protect community resources, including wildlife habitat. The income from these jobs goes directly into the Chiefdom, and it is fair to say that poachers have an equal, if not advantage in applying for CS jobs. The CS role requires physical endurance, knowledge of bushcraft, and a willingness to spend one's work time in the outdoors. People with poaching

experience are naturally inclined to be high performing CS with a change in mindset towards legally earned income and with the passing of training.

BCP's regular investment in service training of CS serves as a deterrent to would-be poachers. The information regarding recurrent training is shared with communities via BCP's community engagement team. These deterrents help would be poachers with decision-making tools to not invest effort into illegal activities with a higher risk of CS intervention.

A key part of the strategy employed is a heavy investment in community projects which improve well-being. For example, investments in water, education, and health services, as well as community transport (such as boats) provide households with indirect improvements in quality of life. Direct improvements in quality of life are provided through BCP's investment in scalable food security safety net and income diversification schemes such as honey and conservation farming.

A further measure to reduce negative impacts is BCP's use of 'Community Covenants' for community projects BCP invests in. These provide a mechanism by which the community can engage with and help would be poachers with social support as an incentive to stop poaching and risk undermining the Covenant or the CFMA which includes a definition of non-performance as poaching.

These measures above are also applicable to illegal charcoal producers. In addition, BCP has initiated a pilot Eco-Charcoal project which supplies legal, sustainable charcoal to the market. The model is being implemented in Rufunsa District under the Lower Zambezi REDD+ Project (LZRP) but the project model is scalable to Open Areas and operates under the principle of "Poachers to Gamekeepers". This principle is to provide illegal charcoal producers with a pathway to becoming legal charcoal producers. Currently, there are no restrictions on people joining the Eco-Charcoal project, and the vision in time is to offer it for expansion to community areas where there is demand and a desire for alternative livelihoods.

Impact on Local Stakeholder Land Use Rights

The land tenure has not changed as a result of the project. As described in section 2.2, the project undertook an extensive consultation process with all of the relevant local stakeholders. The land was previously in GMAs managed by community resources boards (CRBs). The project has helped the CRBs gain additional status as community forest management groups (CFMGs) and helped them create community forest management agreements (CFMAs) with the government that gives them rights to new resources in the area (carbon).

To provide an incentive for better protection of the forests within the CFMAs, BCP has signed agreements with the CRBs stipulating to pay 40 % of net revenue to communities.

Ongoing communication with local stakeholders and grievance redress procedure

BCP maintains a constant presence in the participating chiefdoms and continues to be engaged in awareness-raising activities and various livelihood activities described in section 3.

Additionally, BCP has a well-established and publicly known grievance mechanism that has been designed to address and resolve any problems. All the CFMAs that have been signed by communities have a grievance procedure stipulated covering the contractual agreements regarding the project activity (Appendix A). In addition, a Stakeholder Grievance Response SOP is in place, signed by lead members of the engagement team and signed for as received by each CRB and kept on file (Appendix E). The grievance mechanism is clearly outlined and discussed in community sensitization meetings, and contact information for BCP representatives is included in all public communications. Meeting minutes (written records) from all of the community sensitization meetings document that the grievance mechanism has been explained to the local community representatives in attendance—including their right to receive a response within 30 days, and their right to contact third party arbitrators directly should they have any ongoing concerns. In 2018, BCP updated the Grievance Mechanism from the 2013 version.

Grievances that are submitted to BCP are documented, as are the responses to any such grievances. These documentations are copied to the relevant GRZ office to ensure a third party involvement, to prevent any conflict of interest. Project management will attempt to resolve all reasonable grievances raised, and we commit to providing a written response to grievances within 30 days. In order to track grievances, BCP has established a Grievance Tracker by Chiefdom (Appendix E) which keeps track of dates received and actions taken to close-out of a grievance.

Our SOPs Concerning 1) Community Engagement, and 2) Social Monitoring reference the 2018 Grievance Mechanism as a tool that accompanies these community engagement processes. The formal process for handling grievances is outlined in these documents which are made available to the VVB. The grievance mechanism is also written into all contracts (such as Community Covenants) that are signed between BCP and community representatives, such that BCP and local community members are able to hold each other to account with regard to the delivery of services as per the terms of agreements. The Community Engagement Teams are expected to serve as liaisons between stakeholder communities and the project team. In addition, they are expected to communicate any needs, questions or concerns that either side has.

In the event that community stakeholders have a serious concern or grievance about BCP's Community Engagement Strategy, or if there is an on-going or long-lasting grievance among community stakeholders that BCP has been unable to address, BCP's grievance mechanism allows for the involvement of a neutral third-party arbitrator (including legal counsel) that will be able to clarify or resolve the grievance for either or both sides in the dispute. The preferred

third-party arbitrator, in the event of disputes, would be a representative from an appropriate Non-Governmental Organization with a local presence in Zambia—for example, in the event of grievances concerning land, an organization that deals with land-access and/or land-rights will be involved. If there is a grievance concerning food security, an organization such as the Conservation Farming Unit would be involved. In the event that the community prefers to involve local government, BCP has advised the communities that they are welcome to bring concerns to the District government which is headed by the District Commissioner. BCP has a working relationship with local governments in the Districts of the project zone, and local District government officials have been identified as a mutually-trusted third party for both the stakeholder communities and BCP.

All stakeholders are made aware of grievance procedures at stakeholder meetings, the CFMAs (Appendix A) have a grievance procedure incorporated and feedback has to be given to all grievances raised.

Grievances are documented through the receipt of grievance letters, or meeting minutes. We encourage any verbal grievances to be channelled through Government-recognized local governance institutions such as Community Resource Boards, Traditional Authorities, Cooperatives, or Village Action Groups. The Grievances received are filed digitally in a BCP's 'Grievance Register' Tool (Appendix E). This tool is designed to monitor the grievance close-out process against BCP's '2018 Grievance Mechanism and Stakeholder Grievance Response SOP' (Appendix E). Grievance letters are signed for as received and responded to in writing within 30 days. The government and any other key stakeholders are copied in to ensure that a response is transparent and shared with community institutions. Where a Grievance is raised at a smaller scale, such as a VAG or Zone, the grievance response letter is followed up by a meeting to discuss the response and any follow-up actions needed for closing out the grievance.

Copies of the Stakeholder Grievance Mechanism are shared with Cooperatives, CRBs, VAGs, and signed for as received by each CRB and kept on file.

In addition, all community meetings now have an agenda item titled 'Grievances' to ensure that at each meeting there is a public opportunity to air grievances in a formal, more regular, and minuted forum. In order to continue to reinforce the importance of the Grievance Mechanism, training is specified in the BCP SOP on Stakeholder Grievance Responses for community institutions on an annual basis. BCP's goal is to build community relationships to a very strong level through this process of providing pathways for Grievances to flow more easily, as well as binding BCP to 30-day response periods. There were 2 grievances (1 in Mwanya and 1 in Mnkhanya) received across the 12 Chiefdoms and addressed during this monitoring period. The details of these grievances are available in the grievance registers in Appendix E. The Mwanya grievance was closed while the Mnkhanya grievance is considered open as BCP is still awaiting a response from the CRB, even though they acknowledgement a receipt of BCP's response on the 7th of September 2020. The Mnkhanya CRB raised this grievance because they believed they were unfairly penalized for the 2018 deforestation in the Chiefdom. The CRB

was informed and reminded about the CFMA addendum they signed for stating that their revenue share would be reduced if encroachment breaches were not resolved (see AppendixA_CFMG/ MNKHANYA/ 20180503 FINAL Mnkanya CFMA + Addendum.pdf, page 11 for details). An official letter (Appendix E/ Grievance resolution) signed by BCP's head of operations was sent to the CRB on the 23rd of July 2020 and they acknowledged its receipt on the 7th of September 2020. The CRB decided to accept the reduced revenue as they deliberate on an official response to BCP.

3 IMPLEMENTATION STATUS

3.1 Implementation Status of the Project Activity

The LCFP has developed a wide range of deforestation mitigation and benefit-sharing activities with local stakeholders. These activities fit broadly into three different categories namely infrastructure support and development, improved livelihoods, and income diversification through value addition to non-timber forest products, and thirdly forest encroachment and wildlife monitoring and poaching reduction. Project activities happen in the project area, project zone, and leakage areas shown in Figure 6.




Figure 6. Project area, project zone, and leakage areas where project activities take place

Activity Area 1: Infrastructure Development, Social Service Delivery

Defined Activities:

- Construction and rehabilitation of school infrastructure; classroom blocks and latrines,
- Provision of safe drinking water; through the drilling of new boreholes, rehabilitation of existing boreholes, and improvement of existing wells.
- Provision of boats to facilitate safe river crossing
- Support the delivery of health care services through the provision of clinic furniture and fittings
- Provision of hammer mills, maize and rice shellers

Additional Activities Undergoing Investigation and Further Consultation:

- Roof-based water collection (Self Supply)
- Micro-credit project(s)
- Construction and rehabilitation of health care centers,
- Construction of culverts, drifts

Expected Positive Impacts:

- Reduction in the cost of living
- Increased level of education in communities
- Increased local capacities
- Increased life expectancy
- Reduced child mortality and disease transmission

Potential Negative Impacts:

- Conflicts related to the equitable distribution of benefits

Activity Area 2: Apiculture, Agricultural Improvement, Diversification, and Economic Opportunities

Defined Activities:

- Development of agroforestry demonstration plots to test and demonstrate agricultural multi-cropping, diversification, and intensification.
- Training lead farmers in conservation farming techniques to support follower farmers through the farmer-to-farmer model.
- Hosting of farmer field schools to teach farmers about climate-smart agriculture
- Development of apiary demonstration plots, and train lead farmers (mentors) in hive construction, maintenance, and appropriate apiary and beekeeping techniques.

- Distribution of 6 000 beehives to 16 100 participating households within the project area.
- Supporting poultry and animal husbandry and facilitating the construction of animal enclosures to prevent the spread of diseases and damage to crops

Additional Activities Undergoing Investigation and Further Consultation:

- Supporting the development of horticulture production
- Assistance with the commercialization of agricultural products and Support in crop aggregation for easy access to markets outside the project area
- Land-based aquaculture

Expected Positive Impacts:

- Increased quantity, diversification, and value of crops
- Improved nutritional value of crops
- More sustainable practices (Conservation farming, Beekeeping, and forest management training)
- Reduced pressure on the ecosystem
- Improved resilience to crop failure and market fluctuations
- Increased employment opportunities (Lead Farmers)
- Improved well-being
- Guaranteed market for honey

Potential Negative Impacts:

- Increased cost of living if the value of crops increases
- Conflict related to unequal distribution of benefits and workload

Support to improved agriculture techniques through Conservation Farming

In 2017, LCFP began its conservation farming activities by supporting the work of the Ministry of Agriculture, specifically through the provision of conservation farming extension services. Agreements were signed with the respective territorial Ministry of Agriculture offices within the project zone in the districts listed in Table 3

Table 3. District agreements with the Department of Agriculture.

Location	Date Agreement signed with MoA
Mambwe District	21/11/2016
Nyimba District	15/03/2017
Lundazi District	21/01/2017
Rufunsa District	29/05/2017

Arising from the FPIC community consultative meeting; forests are one of the main sources of livelihood for the local communities with illegal charcoal production, illegal logging, and unsustainable farming methods such as shifting cultivation (“slash and burn”) being the major activities conducted. These activities coupled with the increased in-migration of farmers from the plateau to the valleys, where soils are still fertile, has increased the demand for opening up new farmland within the project area. Conservation Farming was thus one of the activities identified during the needs assessment process as an intervention that would complement LCFP’s conservation activities. This intervention targeted 1 260 households with conservation farming training and extension services within the first year of implementation.

For the 2017 – 2019 farming season, 2247 farmers in the wider area were enrolled by the Ministry of Agriculture to participate and receive extension services in Conservation Farming. During the current monitoring period (2020), a total of 200 new lead farmers (Table 4) were trained in participating LCFP chiefdoms (see appendix B for details).

Table 4. Conservation farmers enrolled in project zone.

Location (Chiefdom)	Number of farmers trained
Nyalugwe	24
Luembe	34
Sandwe	34
Nsefu	9
Mkhanya	10
Malama	8
Jumbe	10
Msoro	10
Mwanya	20
Chitungulu	20
Shikabeta	18
Mpanshya	3

Location (Chiefdom)	Number of farmers trained
Total	200

The main activities that are being supported under this intervention are:

- Promotion of planting of *Faidherbia albida* (Musangu) and other agroforestry species.
- Training of “facilitators” “lead” farmers in participatory research and extension techniques and improved crop production technologies.
- Strengthening of existing farmers’ groups through training in group dynamics, business administration
- Promotion of land management through farmer training in land preparation;

Expected Outcomes:

- Reduced encroachment into the forests under protection through REDD+
- Increased production of high-value crops (soya beans, cowpeas, sunflower).
- Improvements in the income levels of rural households through the sale of surplus grains.
- Enhancement of the nutritional status of farm families, especially the children and women members through increased consumption of pulses.
- Confidence built amongst small-scale producers due to cultivation using sustainable methods and diversifying their food production, and entering into small-scale agri-business practices.
- Reduced dependence on agriculture subsidies and use of artificial fertilizers.
- Enhancement of the knowledge base and skills of small-scale rural producers in modern production, processing and marketing practices.
- Access to the local, regional and national markets ensured for small-scale rural producers through market linkages

Support for the development of Value Chains in Non- timber forest Products

Improved Apiculture techniques:

Whilst beekeeping is regarded as a cottage industry in Zambia, that is well suited for individuals and companies with limited resources for investment, its potential to contribute to the reduction of rural poverty cannot be ignored. According to the Central Statistics Office (2010), the incidence of rural poverty in Zambia is about 80 %. If well organized, beekeeping can contribute to poverty reduction as it increases people’s income.

Although honey hunting and beekeeping have been practiced for a long time by almost all communities in Zambia, beekeeping is only now being promoted as an alternative livelihood for those people that are involved in charcoal production and illegal game hunting, and for those that want an extra income.

Against this background, LCFP conducted a viability assessment in 2016, on the potential to establish honey production value chains within the LCFP project area. Based on the findings of this viability assessment, an agreement was signed with Bee Sweet, to expand honey production to cover the LCFP project zone. Through this intervention, 12 from a target of 11 honey producer- lead farmers (Mentors), received training from Bee Sweet in hive construction and maintenance and apiary management (Table 5).

Table 5. Number of bee mentors trained in the project zone.

District	Chiefdom	No. Mentors trained	Date of Completion of training
Mambwe	Mwanya	3	July 2016
	Jumbe	2	May 2017
	Mnkhanya	1	May 2017
	Msoro	3	August 2017
	Malama	3	August 2017

Through this intervention, 6 000 Kenya topbar beehives were distributed within the LCFP project area to 1,100 beneficiary households (Table 6).

Table 6. Beehive distribution in the project zone.

District	Chiefdom	Target No, of hives to be distributed	Actual No. distributed	Date of last beehive delivery
Mambwe	Mwanya	1000	760	May 2018
Mambwe	Jumbe	1000	1000	August 2017
Mambwe	Mnkhanya	1000	1000	February 2018
Mambwe	Msoro	1000	900	May 2018
Mambwe	Malama	1000	1000	May 2018
Mambwe	Nsefu	1000	375	May 2018
Total		6000	5,035	May 2018

The contract with Bee Sweet ended in April 2020 without renewal. BCP is in the process of conducting a feasibility study for expanding the honey project as well as consulting potential new partners. Meanwhile, the communities are, however, still harvesting the honey and selling to whoever they please.

Expected Outcomes:

- Reduced encroachment into the forests under protection through REDD+ by local communities harvesting honey.
- Increased production of natural honey.
- Improvements in the income levels of rural households through the sale of honey.
- Reduction in the use of traditional hives and falling of trees due to honey hunting.
- Enhancement of the knowledge base and skills of honey producer in modern honey production, processing and marketing practices.
- Confidence built amongst honey producers due to having a guaranteed market for the honey produced.

Support to Infrastructure Development and Social Service Delivery

Construction of School Infrastructure:

In 2016 following the community needs assessment conducted in Luembe and Nyalugwe Chiefdoms, LCFP working with the community of Luembe and Nyalugwe Chiefdoms and the Ministry of Education in Nyimba constructed a 1x2 classroom block at Mkoma Primary School and one teacher's house, as Partnership Impact Projects intended to benefit the community of Mkoma and Mushalira.

In Luembe Chiefdom, the construction of the teacher's house commenced in July of 2016 and completed in January 2017, Whilst the construction of the 1x2 classroom block at Mkoma begun in November 2016 and was completed in May 2017 for use by the community.

Construction of a Mothers Shelter:

In Msoro Chiefdom, one mother's shelter began to be constructed in November 2017. The purpose for this shelter is to make it easier for women in rural places who live far from health posts to receive quality maternity care in a timely manner and encourage women to give birth in a health facility. Some women in the Msoro chiefdom used to walk more than 20 km to the nearest health care facility when they were due for delivery. The project had slow progress in 2019 due to material shortages but construction was completed in 2020. The mother's shelter is projected to benefit more than 400 women.

Support to delivery of Community Social Services:

As part of the community social services support through Partnership Impact Projects, in Mwanya Chiefdom, LCFP procured and supplied 1 fiberglass boat and hospital furniture to benefit the community of Mwanya Chiefdom. The boat provides safe river crossing at Lukusuzi for the community and especially the school children in Mkwela. The hospital furniture and fittings provided was delivered to Mwanya Chiefdom for use at Yakobe Rural Health Post.

In Msoro Chiefdom, LCFP provided three maize shellers, as Partnership Impact Projects intended to benefit the entire community of Msoro. LCFP handed over the maize shellers to the community of Msoro Chiefdom through the community Resources Board, who have stationed each Maize sheller in a specific zone within the Chiefdom for ease of access to the beneficiary local community.

Improved water supply:

Following the community needs assessment conducted during the FPIC meetings to develop the PFMP in October 2015, LCFP drilled six new boreholes to provide clean safe drinking water to the local communities in Jumbe and Kakumbi Chiefdoms. In addition, in February 2016, LCFP commenced works to improve 10 open community wells through the construction of well lining, covers, and installation of hand pumps as water-lifting devices. The projects that have been implemented in the various districts impacted by LCFP since the project start date are shown in Table 7.

Table 7. Infrastructure projects in the project zone.

Location (District)	Description of Intervention	Year started	Date Completed
Lundazi	Provision of fiberglass boat	2016	05/2016
Lundazi	Provision of Furniture and fittings	2016	06/2016
Mambwe	Construction material support towards the construction of Community Guest House	2016	12/2019
Mambwe	Drilling of 6 new boreholes	2016	11/2016
Nyimba	Construction of 1 teachers house	2016	04/2017
Nyimba	Construction of 1x2 classroom block	2016	06/2017

Location (District)	Description of Intervention	Year started	Date Completed
Mambwe	Moulding of 9000 bricks for construction of a secondary school	2017	12/2018
Mambwe	Repairing of the roof for a 1x2 classroom block	2017	12/2019
Mambwe	Construction of Double VIP Latrine	2017	06/2020
Nyimba	Construction of 11 teachers' houses	2017	08/2018
Mambwe	Improvement of 10 open wells	2017	12/2017
Mambwe	Provision of 3 maize shellers	2017	09/2017
Mambwe	Procurement and delivery of three Maize Shellers	2017	09/2017
Lumezi	Construction of clinic staff house	2017	12/2019
Lumezi	Construction of 2 teachers' houses	2017	12/2019
Mambwe	Erection of water storage tank	2017	06/2020
Mambwe	Mothers shelter	2017	10/2020
Nyimba	Procurement of a hammer mill	2017	12/2017
Nyimba	Provision of fiberglass boat	2017	12/2017
Mambwe	Construction of Girls' Dormitory at Chilongozi primary school	2018	12/2018
Sandwe	Construction of 1x3 Classroom Block	2018	04/2020
Rufunsa	Hammer Mill House	2018	12/2018
Nyimba	Procurement of a boat	2018	06/2018
Mambwe	Rehabilitation of 2 teachers' houses	2018	09/2018
Nyimba	Construction of a teacher's house	2018	09/2019
Lundazi	Solar electrification of Mkasanga Health Post	2018	11/2018
Jumbe	Supply of solar panels for computer lessons to a school	2019	10/2020
Lusangazi	Rehabilitation of 1x3 classroom block	2019	11/2019

Location (District)	Description of Intervention	Year started	Date Completed
Nyimba	Rehabilitation of 1 teacher's house	2019	07/2019
Nyimba	Rehabilitation of 1X2 classroom block	2019	12/2019
Mambwe	Construction of 1 x 2 Classroom block	2020	Ongoing
Mambwe	Construction of a Health outreach center	2020	Ongoing

Expected Positive Impacts:

- Reduction in the cost of living
- Increased level of education in communities
- Increased local capacities
- Increased life expectancy
- Increased institutional deliveries and improved antenatal and Postnatal services
- Reduced child mortality and disease transmission

Potential Negative Impacts:

- Conflicts related to the equitable distribution of benefits

Our Theory of Change (Figure 8) around the provision of livelihoods support is that if we can help communities make long term investments in a shared vision for development and demonstrate that those investments are intrinsically linked to the successful long term conservation of forests, then livelihoods in those communities will improve demonstrably and be sustainable, while natural forests will remain intact.

Key risks to providing benefits to the communities include the following:

- Risk of elite capture of benefits, either from REDD+ or from livelihood activities themselves.
- Communities may not grasp the connection between performance (REDD+ forest conservation) and the benefits they receive.
- Households may not benefit enough from REDD+ to halt deforestation.
- Households may “cheat” and take benefits while continuing to deforest.

To address some of these risks BCP is implementing forest and biodiversity protection measures, in addition. Since these risks are complex and difficult to deal with we also forward a Beyond Subsistence Livelihoods approach that:

- Builds the capacity of CRBs to manage financial resources, govern themselves effectively and build a shared vision for development.
- Provides demonstrable, regular benefits that are used to invest in the shared vision for development that benefit the household level.
- Ensures communities understand linkages between receiving REDD+ benefits and long term forest conservation.

This combination of community-based natural resource governance and sustainable livelihoods development will result in long term conservation and sustainable development impacts for these communities.

Our Beyond Subsistence Livelihoods activities are focused on achieving outcomes that will set the stage for achieving development impacts. CRBs need a vision for development implemented through effective and fair governance of the institution. Investments should lead to improved infrastructure and social services (education and health). The private sector should invest in these communities to build mutually beneficial partnerships. This approach requires that all members of the CRB “sign on” to and honor conservation covenants that spell out the responsibilities that go along with the benefits that come from REDD+.

If we can support our community partners to achieve these outcomes then these impacts will flow from our work:

- Increased income at the household level from forest conservation-friendly livelihoods.
- CRB members will understand that deforestation leads to reduced benefits from REDD+.
- CRB members will be empowered to govern effectively.
- There will be no elite capture of REDD+ benefits.
- Households will benefit from improved social services.

In combination with our efforts to build local capacity and responsibility for forest and biodiversity conservation, these livelihoods efforts lead to our ultimate goals of keeping natural forest ecosystems intact and ensuring that community livelihoods are profitable and sustainable.

Activity Area 3: Forest Encroachment and Wildlife Monitoring and Poaching Reduction

BCP provides support to the local CRB village scouts and the Department of National Parks and Wildlife (DNPW) to ensure the protection of the project area from encroachment by monitoring of wildlife and reducing poaching. This activity is also supported by satellite-based Global Land

Analysis and Discovery forest change alerts (GLAD Alerts) from Global Forest Watch and aerial monitoring.

Defined activities:

- Monthly analysis of GLAD Alerts and follow up by Aerial patrols
- Monthly patrols by village scouts along project area boundaries identified as encroachment hotspots.
- Monthly aerial monitoring of wildlife
- Monthly aerial monitoring of encroachment along project boundaries
- Monthly monitoring of high conservation value species
- Monthly anti-poaching activities including removal of snares, counting carcasses, apprehending poachers.
- Community Camera Trap project to improve community engagement and understand communal people's perceptions of human-wildlife conflicts.

Expected Outcomes:

- Quick response to encroachment in the project area
- Rapid resolution of encroachment through the consultation process by local governance structures notably the CRB and chiefs.
- Reduction of encroachment over time as project activities expand and awareness of monitoring activities take hold
- Greater understanding of wildlife populations and threats to wildlife.
- Adapt management to changing wildlife populations.
- Increase in wildlife populations, especially high conservation value species.
- Employment creation for village scouts.
- Reduction of leakage and project emissions.

Thus far monitoring has been rolled out in most of the project area by participating CRBs. BCP has developed an Impact Monitoring Manual which has a chapter that outlines the interaction of satellite-based alerts and aerial and ground-based monitoring. Potential encroachments received as GLAD Alerts are verified by aerial monitoring and recorded using a GPS. This information is then stored in a database and follow up ground monitoring is then actioned by BCP conservation staff. Scouts are given the location of encroachment, once confirmed on the ground and contact made with encroachers, the Community Engagement Team and CRB then follow up and investigate incidences further.

Monitoring has been rolled out in all of the project area and results of aerial monitoring are shared with all CRBs at the end of each month. Figure 7 below is an example of a monthly

Aerial Patrol map for the Mnkhangya Chiefdom and the associated post-flight report is shown in Appendix B, as an example.




Figure 7. Aerial monitoring map of Mnkhangya for the month of September 2020.




Figure 8. BCP Community Theory of Change

All of the above-mentioned activities are connected in some way to reducing the non-permanence risk. By ensuring little deforestation takes place in the project area, community members' shares are benefited by the project, hence reducing opportunity cost risks and activity displacement leakage is limited to a minimum.

New Projects Implemented in 2020.

During the current monitoring period (2020), BCP continued supporting the projects listed above as ongoing or completed in 2020, launched, through CRBs, 2 new infrastructure projects, trained new farmers in conservation agriculture, continued facilitating beekeeping activities for the first quarter, launched a feasibility study for a new beekeeping partner, and launched animal husbandry and poultry livelihood projects.

Infrastructural projects initiated in 2020 are the construction of a 1 x 2 classroom block and a Health outreach center in Mambwe district, Malama Chiefdom. In 2020, BCP started a poultry project under the Agriculture division. The project is called the Community Improved Village Chicken Project which is designed to be a breeding(multiplication) hub of Improved Village Chicken for the area of operation. The Project will focus on the production of Improved Village Chicken with the goal of giving every household in the area 10 improved village chickens each, to keep at their homesteads. This project is piloted in Nyalugwe Chiefdom where a production

hub will be set up and managed by the CRBs. This will be followed by empowering every household with 10 Improved Village Chickens from the hub in villages across whole Chiefdom. Building plans for the poultry houses have been developed and materials have been procured to get construction works to start soon (See Appendix B for supporting media files).

In 2020 BCP is also supporting the Msoro Chiefdom in training farmers in their chosen livelihood projects of goat rearing, poultry, and horticulture. The Msoro CRB is procuring Goats to be distributed to 120 beneficiaries, and will also support the fresh vegetable producers with starter packs for vegetable production. BCP is facilitating a community-based training for the beneficiaries, to be conducted by staff from the Ministry of Agriculture and the Ministry of livestock.

In an effort to improve biodiversity conservation, BCP, in partnership with our biodiversity monitoring partner (Lion Landscapes) piloted a Community Camera Trap project in Chalubilo village near Munyamadzi Game reserve in Nyimba District. The project was set up with the objective of strengthening the link between the benefits that come to communities from REDD+ projects and wildlife conservation, with the ultimate aim of reducing poaching and increasing community engagement with, and awareness of, wildlife conservation issues. The argument is that without clearly establishing this link, it is possible that community members involved in REDD+ projects may receive benefits from the projects whilst still continuing to engage in activities with a negative impact on wildlife populations, both in the REDD zones and in surrounding areas. The camera trap scheme will award communities with direct benefits (in the form of items purchased for households or community projects), based on the amount of wildlife recorded on camera traps placed within community-managed areas. This should provide a very clear and visual link between wildlife presence in the village area and community benefits. Vulnerable species will earn communities more 'points' enabling the targeting of High Conservation Value species for both wildlife monitoring and community engagement purposes. A baseline survey was conducted to investigate the current perceptions of communities toward wildlife and forest conservation (see internal report in Appendix B) and a follow-on survey will be conducted in a year's time.

See Appendix B for selected examples of supporting evidence

3.2 Deviations

3.2.1 Methodology Deviations

MR.97

Demonstration of Forest Age

The methodology requires (in PDR.22) that a digital GIS-based map of the project accounting areas, including aerial or satellite imagery showing that they are comprised of forests or native grasslands as of the project start date and 10 years prior to the project start date. The project did not meet this requirement because it chose to map forests in the project area with PALSAR radar data and the earliest available data for that sensor is from 2007. However, this is justified on several grounds. The project areas are virgin forests that were previously remote and are inaccessible. Thus, there is no history of large disturbances in the area that would have been followed by regeneration between 2005 and 2007. An accurate 2007 forest map of these areas should be virtually indistinguishable from a 2005 map. Additionally, using the 2007 PALSAR imagery results in a much more accurate map of the forests that existed 10 years prior to the start date than would be possible with optical imagery. The optical imagery best suited to mapping the project area is generally from April-June. It is at this time of year, that relatively cloud-free imagery can be obtained when the forests still have leaves and are not dotted with burn scars. Even so, the passing of just a couple of weeks during this period, which is immediately after the rains, results in significant changes in the appearance of the forest in optical imagery. The project initially tried mapping forests with optical imagery but found significant changes between years that were the result of seasonality rather than real changes in forest areas. These effects are much reduced when using PALSAR radar data. This is because, in addition to being cloud penetrating, L band radar has a relatively long bandwidth and thus does not generally interact with the leaves of trees, but does interact with large branches and stems². Finally, VM0009 does not require a remote sensing analysis of an area, but rather to visual show that it is unconverted as of the project start date and 10 years prior. Such an approach is highly subjective since unconverted grasslands and farmlands may at times appear similar. With the PALSAR based analysis, all non-forest areas, whether natural or not were excluded. Thus, using the PALSAR data improved the accuracy of the analysis and did not negatively impact the conservativeness of the quantification of GHG emission reductions or removals. The deviation only affects the monitoring and measuring part of the methodology.

² Mitchard, E. T. A., *et al.* "Using satellite radar backscatter to predict above - ground woody biomass: A consistent relationship across four different African landscapes." *Geophysical Research Letters* 36.23 (2009)

Leakage Plot Protocol

There was a minor deviation of the visual approach for leakage monitoring (Appendix R, VM0009). Instead of Forest Inventory Team members estimating degradation, they were required to geo-reference every felled tree in the permanent plots and the total number of felled trees were compared against the average density of trees/ha in the project accounting area, again avoiding biased estimations/erroneous counting of trees in 1ha plots. This value was then placed in a degradation category as per VM0009. This approach removed all potential bias and greatly improves the robustness and repeatability of degradation monitoring. This deviation does not affect the conservativeness of any emissions reductions as it is in fact an improvement of the prescribed procedure and removes observer bias that could result in degradation in the leakage area being underestimated. The deviation only affects the monitoring and measuring part of the methodology.

Biomass estimation

The project uses two different allometric equations to estimate above-ground biomass. One was developed from data provided by Prof. Chudimayo from Zambian Miombo (see Appendix G) and was tested on trees up to 55 cm DBH. It is used to estimate the biomass of trees up to 63 cm dbh, with the biomass of trees between 55 cm and 63 cm dbh assumed to be equal to a 55 cm dbh tree. Then, a second equation developed by Mugasha et al. in Tanzanian Miombo (see Appendix G) is used to estimate the biomass of trees between 63 cm dbh and 110 cm dbh with trees with a greater than 110 cm dbh assumed to have biomass equal to a 110 cm dbh tree. This parsing is necessary because the methodology requires that the directly measured biomass of the largest tree in the representative sample of destructively harvested trees be greater than the biomass predicted by the equation and that the value of the first-order derivative of the largest tree in the representative sample and inventory not differ by more than 10%. The first selected allometric equation does underpredict the biomass of the largest tree in the representative sample, but the difference of the first-order derivative values was greater than 10%. The second allometric equation doesn't pass the first test (it slightly over predicts the biomass of the largest tree in the sample). However, compared to the Zambian equation, it predicts lower biomass for every size tree. Therefore, the equations were applied as described above to enable the project to make an estimate of the biomass of larger trees that fell outside the range of the size of trees used to develop the equations. Only 33 trees out of 3589 trees in the inventory had a dbh above 55 cm and only 3 had a dbh above 110 cm. Applying the equations in this way is conservative and erases the possibility of the equation overpredicting biomass of trees outside the size classes for which it was tested. This deviation only relates to how biomass is measured for monitoring purposes and doesn't affect any other part of the methodology. It results in a more conservative estimate of biomass and emissions savings. Therefore, it meets the criteria for an acceptable methodological deviation.

Soil Emission Calculations

The VM0009 baseline soil emissions model assumes that SOC in deforested areas will deplete to the same value as the proxy area after 5 years. Project SOC emissions are supposed to be tracked directly through field measurements in encroached areas. However, in the project area, the main drivers of deforestation (smallholder farmers) deliberately choose high fertility areas for conversion with higher than average SOC values. Following the methodology, it would appear that encroachment causes an increase in SOC, which is not consistent with what is actually occurring to soil stocks. To avoid this bias, we conservatively assumed that once encroached, the average SOC stocking per ha in the encroached area becomes the proxy area SOC stocking. This methodological deviation is, therefore, more conservative in calculating emissions reductions from SOC. It does not relate to any other part of the methodology, except for calculating soil carbon stocks in the encroached area. See the master biomass summary spreadsheets in Appendix G for this conservative calculation.

3.2.2 Project Description Deviations

Parameters $t^{[i-1]}$, $t^{[m]}$, $t^{[m-1]}$, $U_B^{[m]}$, $U_{EM}^{[M]}$ were mistakenly excluded from section 3.3.2 of the validated PD but they are monitored during the crediting period. These parameters are included in section 4.2 of this MR and will be included in the PD when it gets to be updated at the 10 years' baseline re-evaluation.

3.3 Grouped Projects

There are no new project instances for this monitoring period.

MR.7 - 8

The project activity start date for the initial project area instance is the same as the project start date: May 1st, 2015. Therefore, the number of days since the project start date for the initial project area instance is 0.

4 DATA AND PARAMETERS

4.1 Data and Parameters Available at Validation

Data / Parameter	α
Data unit	Unitless
Description	Combined effects of β and θ at the start of the historic reference period
Source of data	Reference area and historic reference period
Value applied	0.2188
Justification of choice of data or description of measurement methods and procedures applied	Time and place in which the logistic model is fit. Analysis undertaken as described in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	β
Data unit	Unitless
Description	Effect of time on the cumulative proportion of conversion over time
Source of data	Reference area and historic reference period
Value applied	0.0003271
Justification of choice of data or description of measurement methods and procedures applied	Time and place in which the logistic model is fit. Analysis undertaken as described in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	γ
Data unit	Days
Description	Time shift from beginning of historic reference period to project start date
Source of data	Historic reference period
Value applied	10,589
Justification of choice of data or description of measurement methods and procedures applied	Time in which the logistic model is fit. Analysis undertaken as described in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	λ_{soc}
Data unit	Proportion (unitless)
Description	Exponential soil carbon decay parameter
Source of data	VCS AFOLU default for tropical regions
Value applied	0.2
Justification of choice of data or description of measurement methods and procedures applied	Conservative default based on IPCC value.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	$\sigma_{EM}^{\wedge}$
Data unit	Standard deviation (unitless)
Description	The estimated standard deviation of the state observations used to fit the logistic function
Source of data	Remote sensing image interpretation. Analysis undertaken as described in section 3.2.1 of the project document.
Value applied	0.4273
Justification of choice of data or description of measurement methods and procedures applied	Time and place in which the logistic model is fit. Analysis undertaken as described in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	B
Data unit	Set
Description	The set of all selected carbon pools in biomass. Is a subset of C
Source of data	PDD
Value applied	2
Justification of choice of data or description of measurement methods and procedures applied	AGOT and BGOT, See section 1.1.1 of the project document for justification
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	C
Data unit	Set
Description	The set of all selected carbon pools
Source of data	Monitoring records
Value applied	3
Justification of choice of data or description of measurement methods and procedures applied	AGOT, BGOT, SOC, See section 1.1.1 of the project document for justification
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	J
Data unit	Set
Description	The set of all observations of conversion. When superscripted with a monitoring period, the conversion observations are taken for leakage analysis
Source of data	Remote sensing image interpretation or field observations in the leakage area
Value applied	13,194
Justification of choice of data or description of measurement methods and procedures applied	Analysis undertaken as described in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	M
Data unit	Set
Description	The set of all monitoring periods
Source of data	Monitoring records
Value applied	27
Justification of choice of data or description of measurement methods and procedures applied	The project crediting period is 30 years and after the first verification, the project uses annual verification. Thus there will be 27 verification periods.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	A_{PAA}
Data unit	ha
Description	Area of project accounting area
Source of data	GIS analysis prior to sampling
Value applied	485,495
Justification of choice of data or description of measurement methods and procedures applied	Area within the project area that is on slopes of less than 45%, less than 6.5 km from a road, and was forest at least 10 years before the project start date. Described in more detail in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	A_{PX}
Data unit	ha
Description	Area of proxy area
Source of data	GIS analysis prior to sampling
Value applied	3840
Justification of choice of data or description of measurement methods and procedures applied	Areas converted from forest to non-forest between 2010 and 2017 falling within 2 km of buffer around roads passing through communities favorable to having proxy plots on their lands. Described in more detail in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	n_d
Data unit	unitless
Description	Number of spatial points in the reference area
Source of data	Remote sensing image interpretation
Value applied	2600
Justification of choice of data or description of measurement methods and procedures applied	Value deemed sufficient as per VM0009 to adequately quantify forest state in the reference area. Described in more detail in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	o_i
Data unit	Binary
Description	State observation for the sample point in the reference area
Source of data	Remote sensing image interpretation
Value applied	0 or 1
Justification of choice of data or description of measurement methods and procedures applied	Data collected as per the methodology. Described in more detail in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	P_{LME}
Data unit	Proportion (unitless)
Description	Portion of leakage related to market
Source of data	Analysis of drivers of deforestation (Appendix K)
Value applied	0
Justification of choice of data or description of measurement methods and procedures applied	Few wood products are taken from the project area in the baseline scenario and most farming in the baseline scenario is subsistence.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	q
Data unit	Days
Description	Lag between start of degradation and conversion
Source of data	Consultation with agents of deforestation in near project area in Lusaka province – 28 farmers were questioned to determine how long they usually wait after clearing an area before ploughing it.
Value applied	620
Justification of choice of data or description of measurement methods and procedures applied	Based on observations in the reference area, hence applicable to the project area.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	r_{RS}
Data unit	Unitless
Description	Expansion factor for above-ground biomass to below-ground biomass (root/shoot ratio)
Source of data	Chidumayo, E. N. 2013. Estimating tree biomass and changes in root biomass following clear-cutting of <i>Brachystegia-Julbernardia</i> (miombo) woodland in central Zambia. Environmental Conservation. 42(1), pp. 54 - 63.
Value applied	0.54
Justification of choice of data or description of measurement methods and procedures applied	The root-shoot ratio was determined within a study site that overlaps one of the same provinces the project is in.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	r_U
Data unit	Proportion (unitless)
Description	Onset proportion of conversion immediately adjacent to project area
Source of data	GIS analysis and image interpretation
Value applied	0.084
Justification of choice of data or description of measurement methods and procedures applied	Result of remote sensing analysis described in more detail in section 3.2.1 of the project document.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	t
Data unit	Days
Description	Time since project start date
Source of data	Calendar
Value applied	2,070
Justification of choice of data or description of measurement methods and procedures applied	Project start date is May 1 st , 2015 and the current monitoring period ended December 31 st , 2020.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	t_i
Data unit	Days
Description	The point in time of the observation made at point i
Source of data	Remote sensing image interpretation
Value applied	1-11341
Justification of choice of data or description of measurement methods and procedures applied	The historical reference period stretches from May 4 th , 1986 to May 22 nd 2017, which is 11341 days in total.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	t_{PL}
Data unit	Days
Description	Length of project crediting period
Source of data	PD
Value applied	10957
Justification of choice of data or description of measurement methods and procedures applied	The project crediting period is from May 1st, 2015 to April 30th, 2045 which is equivalent to 10957 days.
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	w_i
Data unit	Unitless
Description	Weight applied to the i th sample point in the reference area
Source of data	Remote sensing image interpretation
Value applied	Varies (see Appendix O)
Justification of choice of data or description of measurement methods and procedures applied	Calculated as specified in VM0009
Purpose of Data	Calculation of baseline emissions
Comments	

Data / Parameter	x_i, y_i
Data unit	Geographic coordinates
Description	Latitude and Longitude of the i th sample point
Source of data	Remote sensing image interpretation
Value applied	Varies (see appendix Appendix O)
Justification of choice of data or description of measurement methods and procedures applied	
Purpose of Data	Calculation of baseline emissions
Comments	

4.2 Data and Parameters Monitored

MR.85-87

Data / Parameter	$A_{P1}^{[m=0]}$
Data unit	ha
Description	Area of project accounting area stratum 1 prior to first verification event
Source of data	GIS analysis prior to sampling
Description of measurement methods and procedures to be applied	GIS analysis removing areas in the project area that were non-forest prior to the project start date, on slopes greater than 45% or in areas farther than 6.5 km from a road.
Frequency of monitoring/recording	First monitoring period / 10 years
Value monitored	485,495
Monitoring equipment	N/A
QA/QC procedures to be applied	Double checking GIS analysis
Purpose of the data	Calculation of baseline emissions
Calculation method	GIS area calculation
Comments	

Data / Parameter	$C_B^{[m]}$
Data unit	tCO ₂ e / ha
Description	Baseline carbon stocks at the end of the current monitoring period
Source of data	Proxy area sampling
Description of measurement methods and procedures to be applied	Proxy area sampling as per the protocol Appendix P.
Frequency of monitoring/recording	20% of plots measured annually
Value monitored	15.6
Monitoring equipment	See Appendix P. Standard vegetation quantification equipment.
QA/QC procedures to be applied	See Appendix P and description in monitoring report.
Purpose of the data	Calculation of baseline emissions
Calculation method	Using standard vegetation ecology plot sampling techniques and subsequent quantification of biomass using allometric equations.
Comments	

Data / Parameter	$C_{B\ BGB}^{[m]}$
Data unit	tCO2e
Description	Carbon not decayed in BGB at the end of the current monitoring period
Source of data	Equation F.32 from VM0009
Description of measurement methods and procedures to be applied	Ongoing forest monitoring as per Appendix P
Frequency of monitoring/recording	Based on peer reviewed literature and prescribed equation in VM0009
Value monitored	18,568
Monitoring equipment	See Appendix P
QA/QC procedures to be applied	See Appendix P
Purpose of the data	Calculation of baseline emissions
Calculation method	Applied equation F.32 in VM0009 3.0
Comments	

Data / Parameter	$C_{B\text{SOC}}^{[m]}$
Data unit	tCO ₂ e
Description	Carbon not decayed in SOC at the end of the current monitoring period
Source of data	Project accounting area sampling and application of equation F.33 from VM0009 3.0
Description of measurement methods and procedures to be applied	Accounting area sampling as per the protocol in Appendix P and application of equation F.33, VM0009 V3.0
Frequency of monitoring/recording	Every monitoring period
Value monitored	600,876
Monitoring equipment	See Appendix P standard soil sampling procedures and equipment.
QA/QC procedures to be applied	See Appendix P
Purpose of the data	Calculation of baseline emissions
Calculation method	Application of equation F.33 VM0009 V3.0 using SOC values from the project accounting area.
Comments	

Data / Parameter	$C_{Bb}^{[m]}$
Data unit	tCO ₂ e / ha
Description	Baseline scenario average carbon stock in selected carbon pools
Source of data	Proxy area sampling
Description of measurement methods and procedures to be applied	Proxy area sampling as per the protocol Appendix P.
Frequency of monitoring/recording	20% of plots measured annually
Value monitored	15.6
Monitoring equipment	See Appendix P. Standard vegetation quantification equipment.
QA/QC procedures to be applied	See Appendix P and description in monitoring report.
Purpose of the data	Calculation of baseline emissions
Calculation method	Using standard vegetation ecology plot sampling techniques and subsequent quantification of biomass using allometric equations.
Comments	

Data / Parameter	$C_{B\ BM}^{[m]}$
Data unit	tCO ₂ e / ha
Description	Baseline carbon stocks in biomass at the end of the current monitoring period
Source of data	Proxy area sampling
Description of measurement methods and procedures to be applied	Proxy area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	At first verification and baseline revision
Value monitored	15.6
Monitoring equipment	See Appendix P
QA/QC procedures to be applied	Review of monitoring records as described in Appendix P and re-sampling of 20% of plots
Purpose of the data	Calculation of baseline emissions
Calculation method	Using standard vegetation ecology plot sampling techniques and subsequent quantification of biomass using allometric equations. Averages calculated as per equation B.9 VM0009 V3.0
Comments	

Data / Parameter	$C_{B\text{SOC}}^{[m]}$
Data unit	tCO ₂ e / ha
Description	Baseline soil carbon stocks at the end of the current monitoring period
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	Once at first verification
Value monitored	210.6
Monitoring equipment	See Appendix P, standard soil sampling equipment
QA/QC procedures to be applied	Review of monitoring records at next baseline re-evaluation
Purpose of the data	Calculation of baseline emissions
Calculation method	Quantification of SOC done according to Annex B.2.6, VM0009 3.0
Comments	

Data / Parameter	$C_P^{[m]}$
Data unit	tCO ₂ e / ha
Description	Project carbon stocks at the end of the current monitoring period
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Plot monitoring as per the protocol in Appendix P
Frequency of monitoring/recording	20% of plots monitored annually
Value monitored	236.2 in intact forest and 15.2 in encroached forest
Monitoring equipment	See Appendix P, standard vegetation sampling equipment
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_P^{[m-1]}$
Data unit	tCO ₂ e / ha
Description	Project carbon stocks at the beginning of the current monitoring period
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	20% of plots monitored annually
Value monitored	236.2 in intact forest and 15.2 in encroached forest
Monitoring equipment	Review of monitoring records, see Appendix G.
QA/QC procedures to be applied	Review of monitoring records, re-sampling of 20% of plots.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_P^{[m=0]}$
Data unit	tCO ₂ e / ha
Description	Project carbon stocks prior to first verification event
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	First monitoring period
Value monitored	236.2
Monitoring equipment	Appendix P describes the plot based monitoring procedure.
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_{P\ 1\ BM}^{[m=0]}$
Data unit	tCO ₂ e / ha
Description	Project carbon stocks in stratum 1 prior to first verification event
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	First monitoring period
Value monitored	236.2
Monitoring equipment	Appendix P describes the plot based monitoring procedure.
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_{PBM}^{[m=0]}$
Data unit	tCO2e
Description	Project carbon stocks in biomass prior to first verification event
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	First monitoring period
Value monitored	114,668,494
Monitoring equipment	Appendix P describes the plot based monitoring procedure.
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_{Pb}^{[m]}$
Data unit	tCO2e / ha
Description	Average carbon in biomass in the project accounting area
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	20% of biomass plots annually
Value monitored	236.2
Monitoring equipment	Appendix P describes the plot based monitoring equipment.
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_{P1b}^{[m]}$
Data unit	tCO ₂ e / ha
Description	Average carbon in biomass for project accounting area stratum 1
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	20% of biomass plots annually
Value monitored	236.2
Monitoring equipment	Appendix P describes the plot based monitoring equipment.
QA/QC procedures to be applied	Review of monitoring records, see Appendix G.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard plot sampling techniques to quantify vegetation and application of allometric equations. Averages calculated using equation B.9 VM0009 V3.0.
Comments	

Data / Parameter	$C_{P\text{ SOC}}^{[m=0]}$
Data unit	tCO ₂ e / ha
Description	Project soil carbon stocks prior to first verification event
Source of data	Project accounting area sampling
Description of measurement methods and procedures to be applied	Project accounting area sampling as per the protocol in Appendix P
Frequency of monitoring/recording	First monitoring period
Value monitored	235.2
Monitoring equipment	Appendix P, standard soil sampling equipment
QA/QC procedures to be applied	Quantification of SOC done according to Annex B.2.6, VM0009 3.0 at soil lab.
Purpose of the data	Calculation of baseline emissions
Calculation method	Quantification of SOC done according to Annex B.2.6, VM0009 3.0 at soil lab.
Comments	

Data / Parameter	$E_{\Delta GER}^{(m)}$
Data unit	tCO2e
Description	GERs for the current monitoring period
Source of data	Area measurements
Description of measurement methods and procedures to be applied	Accounting area plots monitoring as per Appendix P.
Frequency of monitoring/recording	Every monitoring period
Value monitored	1,593,835
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Review of GER calculations
Purpose of the data	Calculation of project emissions
Calculation method	Calculated with equation F.53 as per section 8.4.1 of VM0009 V3.0
Comments	

Data / Parameter	$E_{\Delta GER}^{[i]}$
Data unit	tCO2e
Description	GERs for monitoring period i
Source of data	Area measurements
Description of measurement methods and procedures to be applied	Accounting area plots monitoring as per Appendix P.
Frequency of monitoring/recording	Prior monitoring period
Value monitored	84,543,180
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Review of GER calculations
Purpose of the data	Calculation of project emissions
Calculation method	Calculated with equation F.53 as per section 8.4.1 of VM0009 V3.0
Comments	

Data / Parameter	$E_{\Delta NER}^{(i)}$
Data unit	tCO2e
Description	NERs for monitoring period i
Source of data	Area measurements
Description of measurement methods and procedures to be applied	Accounting area plots monitoring as per Appendix P.
Frequency of monitoring/recording	Prior monitoring period
Value monitored	75,243,415
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Review of NER calculations
Purpose of the data	Calculation of project emissions
Calculation method	Calculated with VCS AFOLU Non-Permanence Risk Tool and equation F.55 as per section 8.4.3 of VM0009 V3.0
Comments	

Data / Parameter	$E_B^{[m]}$
Data unit	tCO2e
Description	Cumulative baseline emissions at the end of the current monitoring period
Source of data	Proxy area measurements
Description of measurement methods and procedures to be applied	Proxy area plots monitoring as per Appendix P and equation F.16.
Frequency of monitoring/recording	Every monitoring period
Value monitored	7,885,723
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation F.16 from VM0009 V3.0
Comments	

Data / Parameter	$E_B^{[m-1]}$
Data unit	tCO2e
Description	Cumulative baseline emissions at the beginning of the current monitoring period
Source of data	Proxy area measurements
Description of measurement methods and procedures to be applied	Proxy area plots monitoring as per Appendix P and equation F.16.
Frequency of monitoring/recording	Prior monitoring period
Value monitored	6,141,808
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation F.16 from VM0009 V3.0
Comments	

Data / Parameter	$E_{B\Delta}^{[m]}$
Data unit	tCO2e
Description	Change in baseline emissions
Source of data	Proxy area measurements
Description of measurement methods and procedures to be applied	Proxy area plots monitoring as per Appendix P and equation F.15.
Frequency of monitoring/recording	Every monitoring period
Value monitored	1,743,915
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation F.15 from VM0009 V3.0
Comments	

Data / Parameter	$E_{B\Delta BGB}^{(i)}$
Data unit	tCO2e
Description	Change in baseline emissions from below-ground biomass during monitoring period i
Source of data	Monitoring the proxy area
Description of measurement methods and procedures to be applied	Proxy area plots monitoring as per Appendix P
Frequency of monitoring/recording	Every monitoring period
Value monitored	28,151,222
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Calculation of above ground biomass using standard vegetation sampling techniques and application of an acceptable root: shoot ratio and application of equation F.10 of VM0009 V3.0, the decay emissions model
Comments	

Data / Parameter	$E_{B\Delta SOC}^{[m]}$
Data unit	tCO2e
Description	Baseline change in emissions from soil carbon
Source of data	Measurement in the project area
Description of measurement methods and procedures to be applied	Soil sampling in project accounting area as per Appendix P
Frequency of monitoring/recording	At first verification
Value monitored	173,194
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Calculation of SOC using standard soil sampling techniques and application of equation F.7 and F.29 of VM0009 V3.0, the SOC decay emissions model
Comments	

Data / Parameter	$E_{B\Delta SOC}^{[i]}$
Data unit	tCO2e
Description	Baseline emissions from soil carbon in monitoring period i
Source of data	Measurement in the project area
Description of measurement methods and procedures to be applied	Soil sampling in project accounting area as per Appendix P
Frequency of monitoring/recording	At first verification
Value monitored	8,750,116
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Calculation of SOC using standard soil sampling techniques and application of equation F.7 and F.29 of VM0009 V3.0, the SOC decay emissions model
Comments	

Data / Parameter	$E_{BBGB}^{[m]}$
Data unit	tCO2e
Description	Cumulative baseline emissions from below-ground biomass at the end of the current monitoring period
Source of data	Measurement in the proxy area
Description of measurement methods and procedures to be applied	Standard vegetation sampling techniques to quantify above ground biomass, application of a root-shoot ratio and a decay emissions model.
Frequency of monitoring/recording	Every monitoring period
Value monitored	2,685,681
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Calculation of above ground biomass using standard vegetation sampling techniques and application of an acceptable root:shoot ratio and application of equation F.10 of VM0009 V3.0, the decay emissions model
Comments	

Data / Parameter	$E_{BGB}^{[m-1]}$
Data unit	tCO2e
Description	Cumulative baseline emissions from below-ground biomass at the beginning of the current monitoring period
Source of data	Measurement in the proxy area
Description of measurement methods and procedures to be applied	Standard vegetation sampling techniques to quantify above ground biomass, application of a root-shoot ratio and a decay emissions model.
Frequency of monitoring/recording	Every monitoring period
Value monitored	2,079,845
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Calculation of above ground biomass using standard vegetation sampling techniques and application of an acceptable root-to-shoot ratio and application of equation F.10 of VM0009 V3.0, the decay emissions model
Comments	

Data / Parameter	$E_{BBM}^{[m]}$
Data unit	tCO2e
Description	Cumulative baseline emissions from biomass at the end of the current monitoring period
Source of data	Measurement in the proxy area
Description of measurement methods and procedures to be applied	See Appendix E
Frequency of monitoring/recording	Every monitoring period
Value monitored	7,693,550
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	Annual monitoring of proxy area. See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Standard vegetation sampling techniques, quantification of deforestation in the reference area and application of equation F.4 and F.24, VM0009 V3.0
Comments	

Data / Parameter	$E_{BSOC}^{[m]}$
Data unit	tCO2e
Description	Cumulative baseline emissions from soil carbon at the end of the current monitoring period
Source of data	Measurement in the project area
Description of measurement methods and procedures to be applied	Standard soil sampling techniques in the proxy area, laboratory analysis and application of the soil decay model.
Frequency of monitoring/recording	At first verification
Value monitored	793,050
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Quantification of soil carbon and application of equation F.9 and F.29, VM0009, V3.0
Comments	

Data / Parameter	$E_{BSOC}^{[m-1]}$
Data unit	tCO2e
Description	Cumulative baseline emissions from soil carbon at the beginning of the current monitoring period
Source of data	Measurement in the project area
Description of measurement methods and procedures to be applied	Standard soil sampling techniques in the proxy area, laboratory analysis and application of the soil decay model.
Frequency of monitoring/recording	At first verification
Value monitored	619,856
Monitoring equipment	See Appendix P, standard plot sampling equipment
QA/QC procedures to be applied	See Appendix P for error correction procedures.
Purpose of the data	Calculation of baseline emissions
Calculation method	Quantification of soil carbon and application of equation F.9 and F.29, VM0009, V3.0
Comments	

Data / Parameter	$E_{BA}^{[m]}$
Data unit	tCO2e
Description	Cumulative emissions allocated to the buffer account at the end of the current monitoring period
Source of data	VCS Non-Permanence Risk Report, See Appendix H
Description of measurement methods and procedures to be applied	See Appendix H – standard VCS procedure used.
Frequency of monitoring/recording	Non-permanence risk revised at every baseline re-assessment.
Value monitored	-781,094
Monitoring equipment	None
QA/QC procedures to be applied	Annual review of risk criteria and disturbance monitoring
Purpose of the data	Calculation of emissions submitted to VCS buffer account
Calculation method	Procedure followed in VCS non-permanence risk tool and emissions allocated to buffer account subtracted from GERs.
Comments	

Data / Parameter	$E_L^{[m]}$
Data unit	tCO2e
Description	Cumulative emissions from leakage at the end of the current monitoring period
Source of data	Measurements in the leakage area(s)
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	None
QA/QC procedures to be applied	See Appendix R, standard vegetation sampling equipment
Purpose of the data	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Calculation method	Application of equation F.44 and F.45 to field data collected.
Comments	

Data / Parameter	$E_L^{[m-1]}$
Data unit	tCO2e
Description	Cumulative emissions from leakage at the beginning of the current monitoring period
Source of data	Measurements in the leakage area(s)
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	None
QA/QC procedures to be applied	See Appendix R, standard vegetation sampling equipment
Purpose of the data	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Calculation method	Application of equation F.44 and F.45 to field data collected.
Comments	

Data / Parameter	$E_{L\Delta}^{[m]}$
Data unit	tCO2e
Description	Change in emissions due to leakage
Source of data	Measurements in the leakage area(s)
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	None
QA/QC procedures to be applied	See Appendix R, standard vegetation sampling equipment
Purpose of the data	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Calculation method	Application of equation F.44 and F.45 to field data collected.
Comments	

Data / Parameter	$E_{L\text{ASF}}^{[m]}$
Data unit	tCO2e
Description	Cumulative emissions from activity-shifting leakage in forested strata at the end of the current monitoring period
Source of data	Measurements in the leakage area(s)
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	None
QA/QC procedures to be applied	See Appendix R, standard vegetation sampling equipment
Purpose of the data	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Calculation method	Application of equation F.44 and F.45 to field data collected.
Comments	

Data / Parameter	$E_{LME}^{[m]}$
Data unit	tCO2e
Description	Cumulative emissions from market leakage at the end of the current monitoring period
Source of data	N/A
Description of measurement methods and procedures to be applied	Land-use by deforestation agents is subsistence and therefore all market leakage is captured by monitoring in activity shifting leakage areas.
Frequency of monitoring/recording	N/A
Value monitored	0
Monitoring equipment	None
QA/QC procedures to be applied	N/A
Purpose of the data	N/A
Calculation method	N/A
Comments	

Data / Parameter	$E_{P\Delta}^{[m]}$
Data unit	tCO2e
Description	Change in project emissions
Source of data	Monitoring records for Forest Fire, Burning, logging, wood products, and natural disturbance events
Description of measurement methods and procedures to be applied	Standard vegetation sampling techniques and remote sensing to determine the extent of fires and other disturbances.
Frequency of monitoring/recording	Every monitoring period
Value monitored	-150,080
Monitoring equipment	Standard vegetation sampling equipment and satellite imagery.
QA/QC procedures to be applied	Remote sensing, patrols and field measurements
Purpose of the data	Calculation of project emissions
Calculation method	Monitoring data from areas of Forest Fire, Burning, logging, wood products, and natural disturbance events and equation F.41 VM0009 V3.0.
Comments	

Data / Parameter	$E_{P\Delta BRN}^{[m]}$
Data unit	tCO2e
Description	Cumulative project emissions due to burning at the end of the current monitoring period
Source of data	Monitoring plots in the project accounting area
Description of measurement methods and procedures to be applied	Application of equation F.42 using burning monitoring data as input.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	Standard vegetation sampling equipment
QA/QC procedures to be applied	Review of monitoring records
Purpose of the data	Calculation of project emissions
Calculation method	Monitoring data from areas of Burning and equation F.42 VM0009 V3.0.
Comments	Biomass burning in the project accounting area is not a project activity

Data / Parameter	$E_U^{[m]}$
Data unit	tCO2e
Description	Cumulative confidence deduction at the end of the current monitoring period
Source of data	N/A
Description of measurement methods and procedures to be applied	Application of equation F.57 which is the a linear combination of weighted standard errors of estimates from baseline emission models and carbon stock measurements.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0
Monitoring equipment	N/A
QA/QC procedures to be applied	Review of calculations
Purpose of the data	Calculation of project emissions
Calculation method	Equation F.57 from VM0009 V3.0
Comments	

Data / Parameter	$P_{L\ DEG}^{[m]}$
Data unit	Proportion (unitless)
Description	Portion of leakage due to degradation at the end of the current monitoring period
Source of data	Monitoring in the leakage area
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	Every monitoring period
Value monitored	0.088
Monitoring equipment	See Appendix R, standard vegetation sampling equipment
QA/QC procedures to be applied	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Purpose of the data	Calculation of leakage
Calculation method	Calculated using equation B.9, VM0009 V3.0. Minimum sample size determined using equation B.31, VM0009 V3.0
Comments	

Data / Parameter	$P_{L\ DEG}^{[m=0]}$
Data unit	Proportion (unitless)
Description	Portion of leakage due to degradation prior to first verification event
Source of data	Monitoring in the leakage area
Description of measurement methods and procedures to be applied	Plot based sampling of leakage area and estimation of degradation.
Frequency of monitoring/recording	First monitoring period
Value monitored	0.0815
Monitoring equipment	See Appendix R, standard vegetation sampling equipment
QA/QC procedures to be applied	See Appendix R, all evidence of tree-felling by humans are geo-referenced and plots photographed
Purpose of the data	Calculation of leakage
Calculation method	Calculated using equation B.9, VM0009 V3.0. Minimum sample size determined using equation B.31, VM0009 V3.0
Comments	

Data / Parameter	$t^{[i-1]}$
Data unit	Days
Description	Time from the project start date to beginning of monitoring period i
Source of data	Monitoring records
Description of measurement methods and procedures to be applied	NA
Frequency of monitoring/recording	Prior monitoring period
Value monitored	0
Monitoring equipment	NA
QA/QC procedures to be applied	NA
Purpose of the data	Calculation of baseline emissions
Calculation method	Count of days in project crediting period
Comments	

Data / Parameter	$t^{[m]}$
Data unit	Days
Description	Time from project start date to end of current monitoring period
Source of data	Monitoring records
Description of measurement methods and procedures to be applied	NA
Frequency of monitoring/recording	Every monitoring period
Value monitored	2,070
Monitoring equipment	NA
QA/QC procedures to be applied	NA
Purpose of the data	Calculation of baseline emissions
Calculation method	Deduct project start date from end of date of current monitoring
Comments	

Data / Parameter	$t^{[m-1]}$
Data unit	Days
Description	Time from project start date to beginning of current monitoring period
Source of data	Monitoring records
Description of measurement methods and procedures to be applied	NA
Frequency of monitoring/recording	Prior monitoring period
Value monitored	1,705
Monitoring equipment	NA
QA/QC procedures to be applied	NA
Purpose of the data	Calculation of baseline emissions
Calculation method	Deduct project start date from end of date of previous monitoring
Comments	

Data / Parameter	$U_B^{[m]}$
Data unit	tCO2e
Description	Total uncertainty in proxy area carbon stock estimate
Source of data	Biomass and soil carbon inventory data, Appendix G
Description of measurement methods and procedures to be applied	Calculation of the standard error of the total of the baseline emissions model, proxy area carbon stocks and accounting area carbon stocks
Frequency of monitoring/recording	Every monitoring period
Value monitored	15,727
Monitoring equipment	NA
QA/QC procedures to be applied	Review of monitoring records
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation B.10 VM0009 v3.0
Comments	

Data / Parameter	$U_{EM}^{[M]}$
Data unit	tCO2e
Description	Total uncertainty in Baseline Emissions Models
Source of data	Forest State Interpretation, Appendix O
Description of measurement methods and procedures to be applied	Calculation of the standard error of the total of the baseline emissions model, proxy area carbon stocks and accounting area carbon stocks
Frequency of monitoring/recording	Every monitoring period
Value monitored	14,616
Monitoring equipment	NA
QA/QC procedures to be applied	Review of monitoring records
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation B.14 VM0009 v3.0
Comments	

Data / Parameter	$U_p^{[m]}$
Data unit	tCO2e
Description	Total uncertainty in project accounting area carbon stock estimate
Source of data	Biomass and soil carbon inventory data, Appendix G
Description of measurement methods and procedures to be applied	Calculation of the standard error of the total of the baseline emissions model, proxy area carbon stocks and accounting area carbon stocks
Frequency of monitoring/recording	Every monitoring period
Value monitored	18,454,409
Monitoring equipment	NA
QA/QC procedures to be applied	Review of monitoring records
Purpose of the data	Calculation of baseline emissions
Calculation method	Equation B.10 VM0009 v3.0
Comments	

4.3 Monitoring Plan

Table 8. Summary of monitoring activities

Monitoring Activity	Timing	Methods
Trespassing and boundary transgressions	Monthly patrols backed up with aerial surveys at least once per dry season.	Scouts patrol the project area on an ongoing basis, it is their core duty
Leakage monitoring	Annually	Forest Inventory team following VM0009 and re-measuring 100% of leakage plots each year as per protocol in Appendix R.

Monitoring Activity	Timing	Methods
Plot measurements	Annually	Forest Inventory Team following VM0009, re-measuring 20% of plots in project accounting and project proxy areas as per protocol in Appendix P. Since all the plots (100%) were measured a year prior to project validation (i.e. 2018), the 20% per year rotation started in 2019. An additional 20% were measured in 2020. Therefore, a 100% rotation will be completed in 2023.
Disturbance monitoring	One a year using satellite imagery from April-May	Remote sensing using Sentinel-2 or Landsat imagery. Followed up with aerial surveys and, or scout patrols.

PDR.122

The principal means of monitoring project emissions is with inventory plots in project accounting areas where above-ground biomass is measured by recording tree dbh. Allometric equations are used to convert the measures to above and below-ground biomass. Soil samples are also collected during the first monitoring period to establish the soil carbon stocks for the project accounting area. VM0009 requires that all such plots must be measured during the first monitoring period and then 20% measured during each subsequent monitoring period. After mapping the project accounting area described in section 3.2.1 of the project document, the project used gis software to generate 122 plots randomly within the project accounting area polygon. One of these plots became encroached, thus biomass monitoring plots used for biomass stocks accounting in the forested area for M1 to M3 monitoring periods are 121 (see **MR.33**). The sample size was estimated based on the variance in biomass inventory plot data from BCP's other REDD project, the Lower Zambezi REDD project.

MR.93

Plot monitoring is conducted in plot locations shown in figure 9, according to the BCP field sampling manual (Appendix P). Optimum plot size and minimum tree diameter were determined under BCP's other project, the Lower Zambezi REDD Project. Circular plots (12m radius) are used due to their simplicity, ease of layout and reduced measurement error. A randomly generated plot location is navigated-to using a handheld GPS or Android Smart Phone. When

the plot location is reached, the centre is permanently marked with a steel rebar driven into the ground.

Trees are identified to species level as far as possible. The use of a generic allometric equation to calculate AGOT mass fortunately negated mistakes or uncertainties with tree species identification.

As explained above, plots are re-measured on a rotating basis, with 20% re-measured per year, however stock estimates are only updated every 5 years after all plots have been re-measured.

In addition to the inventory plots, human and natural disturbances in the project accounting area are mapped using visual interpretation of Sentinel-2 and if needed Landsat data. This is done once a year using the most cloud-free imagery from April-May. This represents the end of the rainy season and the beginning of the dry season. This is generally the best time of the year for mapping woodlands in Zambia as there is less cloud cover, trees generally still have leaves, and the understory grass has started to dry out providing better contrast between grassy and wooded areas. The woodlands in the project area are fire-adapted and fires generally don't cause a massive disturbance. April-May imagery helps avoid mistakenly mapping fire scars as a disturbance when the fire likely only burned the understory grass. With April-May imagery, only permanently damaging fires will be mapped as a disturbance.

When significant disturbances are detected in an area not covered by an inventory plot, a polygon will be drawn around the area and the per hectare emissions factors determined from the plot inventory work will be applied to the area to calculate project emissions.




Figure 9. Accounting, Proxy, and Leakage Plots (MR.91)

PDR.123

Proxy plots are used to estimate residual biomass after conversion and the end point for soil carbon decay. For estimating residual biomass, after mapping the proxy areas as described in section 3.2.1 of the project document, the project generated a random sample of 45 points within the proxy areas. Variability in proxy plots is high since some farmers leave large isolated trees in their farms and invariability, some proxy plots will include these trees. Based on experience from the previous LZRP REDD project, BCP settled on a sample size of just 45 points (Table 10). This is because while the variability with proxy plots is high relative to the proxy plot average, that variability is low relative to the accounting area carbon stocks and thus represents a relatively small portion of the overall uncertainty in baseline emissions.

The same biomass and soil sampling protocols used for accounting areas (Appendix P) were used for proxy areas as well.

Proxy soil measurements were conservatively excluded in M1 and M2. For M3, proxy soil sampling was conducted in areas that represented the end point of conversion and the data was analyzed for SOC accounting. See Appendix C for details.

PDR.124

Leakage plots in the leakage area are used to estimate activity-shifting leakage from the project accounting areas. The project generated a random sample of 25 points within the leakage area where 1 ha leakage plots could be established. Equation B.31 as per VM0009, suggested the minimum number of plots required was 22.

The leakage plot protocol is described in Appendix R.

MR.92

GPS coordinates for all of the accounting area, proxy, and leakage plots can be found in Appendix I.

MR.98

All accounting area, proxy, and leakage plots were measured during monitoring period 1. The project verifies on an annual basis, therefore, measures all leakage plots each year and 20% of the accounting area and proxy plots each year.

Organizational Structure, responsibilities, and competencies

BioCarbon Partners has a team of experts responsible for carbon stock monitoring and standards compliance. As per VM0009, carbon stock monitoring is done using a combination of permanent plots in the project accounting area, proxy area, and leakage area, and remote sensing. Scout teams are used to confirm encroachment and deforestation in the project area as part of the community engagement process to resolve encroachment (Figure 10). The carbon accounting department oversees all forest-related data collection, processing, storage, GIS and remote sensing, and electronic data capture systems with a central database (Figure 10).




Figure 10. BCP Carbon Monitoring Process.

Both the carbon accounting manager and remote sensing and GIS specialist have post graduate degrees with a strong focus on African ecology and collectively have more than 20 years' experience in biological inventories, remote sensing, and GIS.

Data Management

The process followed for field data collection is outlined in Figure 11. It is a feedback system that relies heavily on training, review and good communication. All training is followed by trial runs of the sampling procedure and then actual data collection under supervision. Data is continuously submitted from the field to the carbon accounting department, and feedback is provided if any corrective actions are required. Remote Sensing data does not have a field component, but all data is also stored on Gdrive. Once data has been error checked and cleaned it is safely stored online using Google Drive and then transferred to an online relational database.




Figure 11. BioCarbon Partners data collection, QA/QC and storage process.

MR.90

Quality Assurance and Quality Control

All data submitted to the central database is subjected to quality control by appropriate staff. The majority of field data is collected using digital tools on smartphones and are either directly loaded to the database or saved on Gdrive where it is checked and then transferred to the database.

A set of Standard Operating Procedures and Field Manuals have been developed for all the various aspects of the carbon inventory. As indicated above, BCP has strong systems in place to ensure all carbon-related data is collected according to the required quality standards. Quality Control is embedded in the organizational structure of the Carbon Accounting department (Figure 10).

Continuous feedback from the field, coupled with field visits from senior staff, ensure that errors are identified in a timely fashion and corrected (Figure 11). Spot checks and internal audits are conducted to make sure all data collected is of the highest standard. The new digital data capture system furthermore ensures that errors are identified and rectified immediately, unlike paper-based systems where data often takes weeks to enter and error check. Spot errors are dealt with as per Appendix P.

With regards to GIS and RS, similar procedures are followed although this role resides mainly within the senior management's responsibility.

MR.88

Three forest monitoring teams were used to collect the biomass and SOC data. Each team was led by an experienced member of what was once a single team formed for the assessment of biomass and SOC data in the Lower Zambezi Redd+ Project. This initial team was trained over a period of 12 days in February and September of 2012. They received a refresher 2-day training in December of 2012, June of 2014, and May of 2016. This core team has been collecting data annually for the other REDD project since 2012 and are thus highly experienced.

In order to speed up the carbon inventory work, a second forest monitoring team was formed. Each of the new teams was led by a highly experienced member of team 1 and all new team members received training before starting field work. At the beginning of and half-way through each year, refresher trainings are conducted with the forest monitoring teams.

MR.99

The project uses two allometric equations to estimate above-ground biomass. For the majority of tree stems, a generic miombo equation developed by Chidumayo (2013) at a study site very close to the project area was used:

$$\text{Wood Biomass (kg)} = 0.0446 * \text{DBH}^{2.765}$$

It was based on a destructive sampling of 113 trees of 19 different species (all of which are found in the project accounting area) with a DBH range of 2 to 39 cm.

The other equation used by the project is another general miombo equation developed by Mugasha et al, 2013 (see Appendix P for publication copy):

$$\text{Wood Biomass (kg)} = 0.1027 * \text{DBH}^{2.4798}$$

It was based on destructive sampling in 4 different sites in Tanzania of 167 sample trees of 60 tree species with a DBH range from 1.1 to 110 cm.

MR.100

Having been developed from sample trees in Zambia near the project area, the Chidumayo equation was the more local of the two equations. It also gave higher biomass estimates for all DBHs than the Mugasha equation. Therefore, it was the preferred equation. Unfortunately, it was not validated for trees above 55 cm. Therefore, it was applied to all trees with a DBH of 55 cm or less. It was also applied to trees less than 63 cm DBH, but the DBH of these trees was conservatively changed to be 55 cm since the equation had not been tested on trees larger than 55 cm DBH. This deviation is explained in more detail in section 2.2. The equation was used to estimate 80% of the project area carbon stocks.

For trees between 63 and 110 cm DBH, the Mugasha equation, which was validated for trees up to 110 cm DBH was applied. It was also applied to 3 trees with diameters greater than 110

cm DBH, by changing the DBH of these trees to 110 cm. This deviation is explained in more detail in section 2.2. The equation was used to estimate 20% of the project area carbon stocks.

MR.101

Both equations were used in the same way as for the first monitoring period.

MR.102

As per VM0009, there was no need to validate the Chidumayo equation with destructive harvesting because the equation came from existing published literature and was developed for miombo forests very similar to the project area. However, BCP did conduct some relevant destructive harvesting as part of developing its first REDD+ project in Lusaka province. Additionally, BCP has the destructive harvesting data from Chidumayo's study of miombo biomass allometry in Lusaka province. So, these two datasets were used to validate the Mugasha et al. equation, which comes from further away.

Also, the samples used to develop both equations did not include trees as large as the largest trees in the inventory data and the equations do not pass the first-order derivative test required by VM0009. Therefore, as described in **MR.100** when the equations were applied to a tree with a DBH greater than the range used to develop the equation, the DBH was changed to match the maximum DBH for which the equation was validated. This deviation is described in more detail in section 2.2.

MR.103

Chidumayo (2013) developed the equation through destructive harvesting of study plots located between latitudes 15.2167° and 15.2833°S and longitudes 29.1500° and 29.2333°E, which was miombo woodland in Lusaka province. The sample consisted of 113 trees spanning 19 species, all of which occur in the project and proxy areas.

The Mugasha equation was also developed for miombo from 4 different sites in Tanzania. Out of 156 trees identified at the species level in the Mugasha et al. Dataset, 87 (56%) were species found in the accounting area biomass plots for this project. Out of 165 sample trees identified at the genus level, 141 (85%) were from a genus found in the accounting area inventory plots. Thus, there was a large number of species and genus overlap between the project accounting area and the Mugasha et al. 2013 sample trees, showing that miombo in Tanzania is similar. Additionally, the equation appears to be conservative relative to the Chidumayo equation and predicts less biomass for any DBH than the Chidumayo equation.

MR.104

The Chidumayo equation did not require validation with destructive harvesting as it was developed from miombo sites in the center of Lusaka province within 60 km of the project area. Thus, the destructive harvesting data from the Chidumayo study and 7 additional trees destructively harvested by BCP were used to validate the Mugasha equation.

MR.105

Chidumayo (2013) developed the equation through destructive harvesting of study plots located between latitudes 15.2167° and 15.2833°S and longitudes 29.1500° and 29.2333°E, which was miombo woodland in Lusaka province within 60 km of the project accounting area. The diameter at breast height (DBH) range for the Chidumayo model was 2-39 cm and it was developed from a sample size of 113 destructively sampled trees covering 19 species, including most of the common species in the project accounting area. BCP then destructively harvested 7 more trees to bring the size range up to 55 cm DBH.

BCP has the original data from the author and have made it available to the VVB (Appendix G). As part of the work to establish its first REDD+ project, BCP destructively sampled another seven trees of various species to extend the diameter range of the Chidumayo equation to 55 cm (Table 9). The procedures followed for destructive harvesting are described in Appendix P and was developed under the guidance of Professor Chidumayo.

Table 9. Results of allometry validation and diameter range expansion.

Species	DBH (cm)	Total dry mass (kg)	Mass Predicted by equation (kg) (Chidumayo 2013)	Latitude	Longitude
<i>Brachystegia boehmii</i>	49	2750	2143	-15.3672	29.08735
<i>Brachystegia boehmii</i>	48	2838	1957	-15.3654	29.08534
<i>Brachystegia boehmii</i>	42	1236	1346	-15.3627	29.08307
<i>Brachystegia spiciformis</i>	41	1141	1318	-15.3678	29.08696
<i>Brachystegia utilis</i>	43	2212	1462	-15.3627	29.08266
<i>Brachystegia utilis</i>	48	2006	2030	-15.3635	29.08613
<i>Parinari curatellifolia</i>	55	3823	2950	-15.3654	29.08537
Total Mass		16006	13206		

MR.106

The field protocol is available in Appendix P.

MR.107

The field protocol (Appendix P) was based on the methods used by Chidumayo (2013) to develop the original equation. It is a methodical and robust approach that is conservative. The same wet-dry mass ratio as used by Chidumayo (2013) was applied.

MR.108

As shown in Appendix G, the Chidumayo equation predicts 10% less biomass than the cumulative measured biomass of the destructively sampled trees. Thus, it is acceptable under VM0009. The Mugasha equation is also acceptable under this condition, predicting 25% less biomass than the cumulative measured biomass of the destructively sampled trees (Appendix G).

5 QUANTIFICATION OF GHG EMISSION REDUCTIONS AND REMOVALS

5.1 Baseline Emissions

MR.95

Table 10. Estimated carbon stock, standard error of the total for each stock, and the sample size for each stratum in the area selected.

Parameter	Project Accounting Area		Proxy Area	
	Forest (AGOT + BGOT)	Soil	Proxy Area (AGOT + BGOT)	Proxy Area Soil*
Plots (P)	121	25	45	25
Total Possible plots (N _{p,k})	42,657,269	42,657,269	339,531	24032
C	113,993,943	114,122,390	59,760	57,251
U (B.10) per stratum	9,801,270	15,636,963	15,411	3,138

MR.10

Baseline emissions ($E_{(B\Delta)}^{[m]}$) for the current monitoring period (January 1st, 2020 to December 31st, 2020) are summarized in Table 11. Equation F.15 was used to calculate these baseline emissions. Cumulative baseline emissions were calculated using a logistic deforestation model, based upon a point interpretation of forest state in the reference area applying equation F.16 from VM0009 v3.0.

Table 11. Baseline emissions summary for the third monitoring period (see Appendix G for calculations).

Monitoring Period	Carbon Pool	Baseline Emissions (tCO2e)
M3	AGOT	1,080,015
M3	BGOT	605,836
M3	SOC	58,064
Total		1,743,915

MR.11

Total Cumulative baseline emissions from prior monitoring periods were 6,141,808 tCO2e. Refer to Appendix G for calculations.

MR.12

Cumulative baseline emissions for each selected pool ($E_{B\Delta}^{[m]}$ and $E_{B\Delta}^{[m]}$) and undecayed carbon ($C_{B\Delta}^{[m]}$, $C_{B\Delta}^{[m]}$) as of the current monitoring period are summarized below.

See Appendix G for calculations.

$$E_{B\Delta}^{[m]} = 7,693,550 \text{ tCO2e}$$

$$E_{B\Delta}^{[m]} = 793,050 \text{ tCO2e}$$

$$C_{B\Delta}^{[m]} = -18,568 \text{ tCO2e}$$

$$C_{B\Delta}^{[m]} = -600,876 \text{ tCO2e}$$

MR.15-17

Baseline emissions from biomass for the current monitoring period are based on the average carbon stock in selected carbon pools from AGOT, BGOT given by equation F.17 for the accounting area and F.18 for the proxy area. There is only one stratum with a carbon stock of 236.2 tCO₂e. The proxy area (baseline scenario) carbon stocks are 15.6 tCO₂e.

Cumulative baseline emissions from biomass $E_{B\text{BM}}^{[m]}$ for the current monitoring period were calculated by equation F.24 from VM0009 V3.0. See Appendix G for calculations.

7,693,550 tCO₂e

Current baseline emissions from SOC ($E_{(B \Delta \text{SOC})}^{[m]}$) as of the current monitoring period were calculated with equation F.29. See Appendix G for calculations.

793,050 tCO₂e

Cumulative baseline emissions from biomass $E_{B\text{BM}}^{[m]}$ for all prior monitoring periods were 6,007,699 tCO₂e

See Appendix G for calculations.

MR.26

Carbon stored in non-decayed BGB ($C_{B\text{BGB}}^{[m]}$) for the current monitoring period was calculated using equation F.32. See Appendix G for calculations.

22,628 tCO₂e

MR.27

Cumulative baseline emissions from BGB for the current monitoring period ($E_{B\text{BGB}}^{[m]}$) were calculated using equation F.30. See Appendix G for calculations.

2,685,681 tCO₂e

MR.28

Cumulative baseline emissions from BGB ($E_{B\text{BGB}}^{[m]}$) for all prior monitoring periods were calculated using equation F.30. See Appendix G for calculations.

2,079,845 tCO₂e

MR.29

Carbon stored in non-decayed SOC for the current monitoring period ($C_{B\text{SOC}}^{[m]}$) was calculated using equation F.33. See Appendix G for calculations.

-115,131 tCO₂e

5.2 Project Emissions

MR.32

Major disturbances (generally, clearing for cropland preparation) in the project area were hand-digitized from mostly cloud-free Sentinel-2 imagery from April-May, 2020 in comparison to April-May, 2019. Maps of the boundaries of these areas are shown in Figures 12, 13, and 14. The imagery was obtained from Earth Engine, exported to Google Cloud as map tiles (script provided to VVB), and then opened in QGIS where imagery from different years was compared to identify changes and polygons were drawn around the changes. Table 12 shows the breakdown of the disturbance areas by chiefdom and conservancy.

Table 12. Results of disturbance mapping in the project area

Area Name	Clearing in 2020 (ha)
Chitungulu	0
Jumbe	30.77
Luembe	2.17
Malama	0
Mnkhanya	266.48
Mpanshya	0.67
Msoro	243.57
Munyamadzi	0
Mwanya	7.71
Nsefu	0
Nyalugwe	0
Pia Manzi	0
Sandwe	59.82

Area Name	Clearing in 2020 (ha)
Shikabeta	0
Total	611.19

MR.33

The disturbed stratum from the M1 to M3 periods represented just 0.63 % of the project accounting area. By random chance, one of the original permanent sample plots fell into the disturbed area and was measured after disturbance. Therefore, in order to have sufficient plots to calculate variance, one more random plot location was selected inside the disturbed area and measured as per Appendix P.

Current emissions from changes in project carbon stocks are calculated with equation F.41 VM0009 v3.0. After restratification (Table 13), the project accounting area stocks at the end of this monitoring period were equal to 228,116,333 tCO₂e (Appendix G) compared to 228,266,413 tCO₂e* at the end of the previous monitoring period (M2). Thus project emissions for this monitoring period were -150,080 tCO₂e

Table 13. Project accounting area stocks at the end of the current monitoring period

Parameter	Project Accounting Area			
	Forest Stratum (AGOT + BGOT)	Forest Stratum (Soil)	Disturbed Stratum (AGOT + BGOT)	Disturbed Stratum (Soil)
Plots (P)	121	25	2	25
Total Possible plots (N _{p,k})	42,657,269	42,657,269	269,914	269,914
C	113,947,492.6	113,479,387	46,450.7	643,003
U (B.10) per stratum	9,801,160.3	15,636,466	46,450.5	124,653

* Value is different from that reported in M2 Monitoring report because SOC was conservatively excluded by then.




Figure 12. Project accounting area clearings in the Southern part of the project area.




Figure 13. Project accounting area clearings in the Central part of the project area.




Figure 14. Project accounting area clearings in the Northern part of the project area.

5.3 Leakage

MR.44

The primary leakage mitigation strategies of the project are improving agricultural techniques with conservation farming and agroforestry and promoting alternative livelihoods that don't depend on forest clearing such as beekeeping. See section 4.3 of this report for more detailed descriptions of the leakage mitigation activities employed by this project. Based on the experience of BCP's other REDD+ project in the Lusaka Province, which employed similar leakage mitigation activities and has not experienced any leakage in 10 years, it is assumed that these activities will also be effective at preventing leakage from the LCFP project area.

MR.48

Under VM0009 V3.0, cumulative emissions from activity-shifting leakage ($E_{(LASF)}^{[m]}$) for the current monitoring period are 0.

MR.49

Cumulative emissions from activity-shifting ($E_{(LAS)}^{[m]}$) for the prior monitoring periods are 0.

MR.56

The parameter ($p_{(L\ DEG)}^{[m]}$) for the current monitoring period was estimated using equation B.9. The calculations can be found in Appendix G.

$$p_{(L\ DEG)}^{[m]} = 0.088$$

MR.57

For the first monitoring period, $p_{(L\ DEG)}^{[m=0]} = 0.0815$

MR.63

BCP is a project proponent representing the private land-owners in this project. BCP doesn't own any land, but is the project proponent in one other REDD+ project in the country involving a private land-owner. The management plans and land-use of land in that REDD+ project have not changed as a result of this project.

The community resource boards (CRBs) are the project proponents for the project areas under community forest management agreements (CFMAs). The project areas are the only lands under their control.

5.4 Net GHG Emission Reductions and Removals

MR.65

GERs (Net GHG emissions or removals in Table 14) for the current monitoring period were calculated using equation F.53 as per section 8.4.1 of VM0009 V3.0 (see Appendix G).

1,593,835 tCO₂e

MR.66

GERs (Net GHG emissions or removals) for the prior monitoring period were calculated using equation F.53 as per section 8.4.1 of VM0009, v3.0 (see Appendix G).

1,534,409 tCO₂e*

MR.67




Figure 15. Graph of GERs by monitoring year.

Table 14. Net GHG emissions reductions or removals for the current monitoring period

Year	Baseline emissions or removals (tCO ₂ e)	Project emissions or removals (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Net GHG emission reductions or removals (tCO ₂ e)	Buffer pool allocation	VCUs eligible for issuance
2020	1,743,915	-150,080	0	1,593,835	-175,322	1,418,513
Total	1,743,915	-150,080	0	1,593,835	-175,322	1,418,513

* Value is different from that reported in M2 Monitoring report because SOC was conservatively excluded by then.

MR.68

$U_B^{[m]}$ - Total uncertainty in proxy area carbon stock estimate = 15,727 tCO₂e

$U_{EM}^{[m]}$ - Total uncertainty in Baseline Emissions Models = 14,616 tCO₂e

$U_P^{[m]}$ - Total uncertainty in project accounting area carbon stock estimate = 18,454,409 tCO₂e

$E_u^{[m]}$ - Total uncertainty = -32,086 = 0

There was no confidence deduction as the uncertainty was insignificant.

MR.69

$U_B^{[m]}$ was calculated with equation B.10 VM0009 V3.0

$U_{EM}^{[m]}$ was calculated with equation F.14 VM0009 V3.0

$U_P^{[m]}$ was calculated with equation B.10 VM00309 V3.0

$E_u^{[m]}$ was calculated with equation F.57 VM0009 V3.0

For more details, see Appendix G.

MR.74

NERs (VCUs as per VCS) generated for the current monitoring period were calculated using equation F.55 from VM0009 V3.0 and are reported in Table 14.

MR.75

NERs for the M2 monitoring period were 1,365,623 tCO₂e*

* Value is different from that reported in M2 Monitoring report because SOC was conservatively excluded by then.

MR.76




Figure 16. Graph of NERs by monitoring year.

MR.77

VCS Non-Permanence Risk Assessment Tool V4.0 (Appendix H) was used to calculate buffer account allocation, calculated as GERs x Non Permanence Risk score (11%) = -175,322 tCO2e.

MR.78

Please see Appendix H for non-permanence risk calculations using the VCS Non-Permanence Risk Assessment Tool V4.0.

MR.82

See Table 14 for quantified NERs by vintage year for the current monitoring period. See Appendix G for calculations.

MR.83

The ex-ante estimated NERs for this monitoring period were 1,546,122 tCO2e compared to an ex-post estimate of 1,418,513 tCO2e.

MR.84

The difference between ex-ante and ex-post estimates is primarily due to the inclusion of SOC for this monitoring period using actual LCFP soil samples data rather than the estimates based on data borrowed from the LZRP project that were used for the projections at project validation.

6 APPENDICES

Appendix A Community Forest Management Agreements and Communication Agreement.
Confidential

Appendix B Project Implementation Status Support Documents. Public

Appendix C Proxy Soil Sampling and Analysis. Confidential

Appendix E BCP Community Engagement SOPs and Monitoring Systems. Confidential

Appendix G Emissions Reductions Calculations. Confidential

Appendix H VCS Non-permanence risk assessment. Public

Appendix I Spatial Data. Confidential

Appendix K Drivers and Agents of Deforestation Study Report

Appendix O Cumulative Deforestation Model. Confidential

Appendix P Biomass and Soil Sampling Protocol. Confidential

Appendix R Leakage Monitoring Protocol. Confidential

7 ANNEX 1: LIST OF VM0009 V3.0 MR REQUIREMENTS APPLICABLE TO F-U3 BASELINE TYPE

MR#	Category	Applicable to Project
MR.1	Spatial Project Boundaries	Yes
MR.2	Temporal Project Boundaries	Yes
MR.3	Temporal Project Boundaries	Yes
MR.4	Grouped Projects	Yes
MR.5	Grouped Projects	Yes
MR.6	Project Accounting Areas	Yes
MR.7	Determining t_{PAI}	Yes
MR.8	Determining t_{PAI}	Yes
MR.9	Determining x_{PAI}	No. No covarites to conversion were used.
MR.10	Baseline Emissions	Yes
MR.11	Baseline Emissions	Yes
MR.12	Baseline Emissions	Yes
MR.15	Applying the Spatial Algorithm	Yes, but there is only one stratum
MR.16	Applying the Spatial Algorithm	Yes, but there is only one stratum
MR.17	Applying the Spatial Algorithm	Yes, but there is only one stratum
MR.21	Carbon Not Decayed in DW	No. All biomass is burned in baseline scenarios

MR.22	Carbon Not Decayed in DW	No. All biomass is burned in baseline scenarios
MR.23	Carbon Not Decayed in DW	No. All biomass is burned in baseline scenarios
MR.24	Carbon Not Decayed in DW	No. All biomass is burned in baseline scenarios
MR.25	Carbon Not Decayed in DW	No. All biomass is burned in baseline scenarios
MR.26	Carbon Not Decayed in BGB	Yes
MR.27	Carbon Not Decayed in BGB	Yes
MR.28	Carbon Not Decayed in BGB	Yes
MR.29	Carbon Not Decayed in SOC	Yes
MR.30	Carbon Stored in Wood Products	No. No timber harvesting in baseline
MR.31	Carbon Stored in Wood Products	No. No timber harvesting in baseline
MR.32	Emissions Events in Project Area	Yes
MR.33	Emissions Events in Project Area	Yes
MR.34	Emissions from Burning from Project Activities	No. No biomass burning in project activities
MR.35	Carbon Stored in Wood Products from Project Activities	No. Timber harvesting is not a project activity
MR.36	Carbon Stored in Wood Products from Project Activities	No. Timber harvesting is not a project activity
MR.37	Carbon Stored in Wood Products from Project Activities	No. Timber harvesting is not a project activity

MR.38	Livestock Grazed in the Project Area	No. Livestock grazing is not permitted in the project area and unpermitted grazing was determined to be de minimus.
MR.39	Livestock Grazed in the Project Area	No. Livestock grazing is not permitted in the project area and unpermitted grazing was determined to be de minimus.
MR.40	Livestock Grazed in the Project Area	No. Livestock grazing is not permitted in the project area and unpermitted grazing was determined to be de minimus.
MR.41	Synthetic Fertilizer in the Project Area	No. Project activities do not include the use of synthetic fertilizers.
MR.42	Synthetic Fertilizer in the Project Area	No. Project activities do not include the use of synthetic fertilizers.
MR.43	Synthetic Fertilizer in the Project Area	No. Project activities do not include the use of synthetic fertilizers.
MR.44	Leakage Mitigation Strategies	Yes
MR.45	Commodity Production for Leakage Mitigation	No. The baseline scenario is subsistence
MR.46	Commodity Production for Leakage Mitigation	No. The baseline scenario is subsistence
MR.47	Commodity Production for Leakage Mitigation	No. The baseline scenario is subsistence
MR.48	Estimating Emissions from Activity-Shifting Leakage	Yes
MR.49	Estimating Emissions from Activity-Shifting Leakage	Yes
MR.50	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area

MR.51	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area
MR.52	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area
MR.53	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area
MR.54	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area
MR.55	Change to the Activity-Shifting Leakage Area	No. No change to activity-shifting leakage area
MR.56	Estimating $p_{L\text{ DEG}}$	Yes
MR.57	Estimating $p_{L\text{ DEG}}$	Yes
MR.58	Estimating $p_{L\text{ CONG}}$	No. No grassland in project area
MR.59	Estimating $p_{L\text{ CONG}}$	No. No grassland in project area
MR.60	Determining Emissions from Market Leakage	No. The baseline scenario is subsistence
MR.61	Determining Emissions from Market Leakage	No. The baseline scenario is subsistence
MR.62	Determining Emissions from Market Leakage	No. The baseline scenario is subsistence
MR.63	Ensuring No Leakage Within Project Proponent's Ownership	Yes
MR.65	Quantification of GERS	Yes
MR.66	Quantification of GERS	Yes

MR.67	Quantification of GERS	Yes
MR.68	Confidence Deduction	Yes
MR.69	Confidence Deduction	Yes
MR.72	Reversal Event	No. No reversal occurred
MR.73	Reversal Event as a Result of Baseline Reevaluation	No. No baseline reevaluation occurred
MR.74	Quantification of NERs for a PAA	Yes
MR.75	Quantification of NERs for a PAA	Yes
MR.76	Quantification of NERs for a PAA	Yes
MR.77	Buffer Account	Yes
MR.78	Buffer Account	Yes
MR.79	Quantification of NERs across PAAs	No. There is currently only 1 PAA
MR.80	Quantification of NERs across PAAs	No. There is currently only 1 PAA
MR.81	Quantification of NERs across PAAs	No. There is currently only 1 PAA
MR.82	Vintages	Yes
MR.83	Evaluating Project Performance	Yes
MR.84	Evaluating Project Performance	Yes
MR.85	Data and Parameters Monitored	Yes
MR.86	Data and Parameters Monitored	Yes
MR.87	Data and Parameters Monitored	Yes
MR.88	Description of the Monitoring Plan	Yes

MR.89	Description of the Monitoring Plan	No. No project activity with biomass burning
MR.90	Description of the Monitoring Plan	Yes
MR.91	Description of the Monitoring Plan	Yes
MR.92	Description of the Monitoring Plan	Yes
MR.93	Description of the Monitoring Plan	Yes
MR.94	Description of the Monitoring Plan	No. No new equations were developed
MR.95	Description of the Monitoring Plan	Yes
MR.96	Description of the Monitoring Plan	No. Timber harvesting is not a project activity
MR.97	Description of the Monitoring Plan	Yes
MR.98	Description of the Monitoring Plan	Yes
MR.99	Sources of Allometry	Yes
MR.100	Sources of Allometry	Yes
MR.101	Sources of Allometry	Yes
MR.102	Sources of Allometry	Yes
MR.103	Sources of Allometry	Yes
MR.104	Validating Previously Developed Allometry	Yes
MR.105	Validating Previously Developed Allometry	Yes
MR.106	Validating Previously Developed Allometry	Yes

MR.107	Validating Previously Developed Allometry	Yes
MR.108	Validating Previously Developed Allometry	Yes
MR.109	Validating Newly Developed Allometry	No. No new allometric equations were developed.
MR.110	Validating Newly Developed Allometry	No. No new allometric equations were developed.
MR.111	Validating Newly Developed Allometry	No. No new allometric equations were developed.
MR.112	Validating Newly Developed Allometry	No. No new allometric equations were developed.
MR.113	Validating Newly Developed Allometry	No. No new allometric equations were developed.